

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 041 HASKELL NW 1/4 NW 1/4 SE 1/4 27 T 29 S R 34 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM SATANTA, 3 MILES NORTH, 1-1/2 MILES WEST, 1/2 NORTH

2 WATER WELL OWNER: MURPHY DUANE  
 RR#, St. Address, Box #: 200 MURPHY STREET Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: SUBLETTE, KS 67877-0756 Application Number: 22,563

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 549 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 308 ft. below land surface measured on mo/day/yr 09/10/96  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 0 ft., and in. to 0 ft.  
 WELL WATER WAS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 0 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 32 lbs/ft. Wall thickness or gauge No. 219  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 264 ft. to 324 ft., From 419 ft. to 489 ft.  
 From 349 ft. to 389 ft., From 509 ft. to 549 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 550 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT  
 Grout intervals: From 3 ft. to 11 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
			517	240	CHLORAMATED SAND
			240	11	CLAY LIKE MATERIAL
			11	3	CONCRETE
			3	0	SURFACE MATERIAL
			0	0	
			0	0	
			0	0	
			0	0	
			0	0	
			0	0	

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Plugged under my jurisdiction and was completed on (mo/day/year) 09/12/96 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/12/96  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)