

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NE 1/4 NE 1/4 SW 1/4 23 T 29 S R 34 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SATANTA, 4 1/2M N & 1/2M W TO LOCATION.

2 WATER WELL OWNER: KIRBY CLAWSON

RR#, St. Address, Box #: RT. 1 BOX 65F

City, State, ZIP code: SATANTA, KS 67870-

Board of Agriculture, Division of Water Resources

Application Number: 14509 4 26, 848

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 664 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 335 ft. below land surface measured on mo/day/yr 07/29/96
 Pump test data: Well water was 395 ft. after 2 hours pumping 930 gpm

Estimated Yield 900 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 664 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 664 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .25

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 381 ft. to 661 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 664 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 520 ft. to 664 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTH How many feet? 280

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	BRWN SANDY CLAY			
20	34	FINE-MED SAND CLAY CALICHE			
34	249	BRWN SANDY CLAY FN-ME-CRS SAND GRAVEL			
249	287	BRWN SANDY CLAY SAND STREAKS LIMESTONE			
287	421	FN-ME-CRS SAND BRWN CLAY STRKS GRAVEL			
421	459	BRWN SANDY CLAY BRWN CLAY STRKS			
459	501	FINE SAND BRWN CLAY STRKS			
501	552	FN-ME-CRS SAND GRAVEL BRWN CLAY STRKS			
552	600	SOAPSTONE CEMENTED SAND			
600	626	SOAPSTONE BROWN CLAY FEW SAND STRKS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/23/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/19/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NE 1/4 NE 1/4 SW 1/4	23	T 29 S	R 34 W

2 WATER WELL OWNER: KIRBY CLAWSON
RR#, St. Address, Box #: RT. 1 BOX 65F
City, State, ZIP code: SATANTA, KS 67870-

Board of Agriculture, Division of Water Resources
Application Number: 14509

FROM	TO	LITHOLOGIC LOG
626	664	SOAPSTONE FINE-MED SAND BRWN CLAY STRKS

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/23/96 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/19/96
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Richman