

The
Professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Carl Pickens
Haskell County
11-5-87

Location: NW $\frac{1}{4}$ 15-29-34 - Haskell Co.

From Santa Fe Feeders - 9 W., 2 S.,
 $\frac{1}{4}$ E., $\frac{1}{8}$ S., 100' W. & 150' S. of
old well.

Static Water Level - 318'

Test #1

0	2	Top soil
2	48	Brown clay
48	66	Fine to medium sand - streak of coarse gravel - loose
66	95	Fine to medium sand & gravel - 15% clay
95	127	Medium to coarse gravel - loose
127	147	Brown clay
147	189	Fine to medium sand & gravel
189	198	Brown clay
198	222	Fine to medium sand & gravel
222	244	Brown clay
244	271	Brown clay - small streak of sand
271	275	Fine to medium sand & gravel
275	305	Brown clay
305	342	Blue clay - sticky
342	379	Fine to medium sand & gravel - loose
379	382	Brown clay
382	390	Fine to medium sand & gravel
390	396	Brown clay
396	402	Fine to medium sand & gravel
402	425	Brown clay
425	437	Brown clay - white rock mixed - no good
437	471	Brown sandy clay
471	522	Fine to medium sand gravel yellow brown rock mixed - tight
522	534	Yellow clay
534	540	Yellow clay
540	544	Shale