

DRILLERS TEST LOG

CUSTOMER'S NAME: Joseph Ruby **DATE:** 6/3/89
STREET ADDRESS: 500 Pike **TEST #** 1 **E. LOG** Yes
CITY & STATE: Sublette, Ks. 67877 **DRILLER** Wildeman
COUNTY Haskell **QUARTER** NE **SECTION** 15 **TOWNSHIP** 29 **RANGE** 34

LOCATION 125' South of the old well.

PAGE 1

WELL LOCATION

Z	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL:
	From	Pay	TO		Proposed Well Depth:
	0		2	Top soil.	
	2		42	Brown sandy clay, Caliche & fine sand streaks.	
	42		67	Sand fine to medium coarse. Small to large gravel. (Loose & rough in places. Used water).	
	67		73	Brown clay.	
	73		79	Sand fine to medium & clay streaks.	
	79		105	Sand fine to medium coarse. Small to large gravel. (Loose & rough in places. Used water).	
	105		120	Sand fine to medium coarse. Small to medium gravel.	
	120		133	Brown clay & few rock ledges.	
	133		140	Sand fine to medium coarse, Small gravel.	
	140		164	Brown, yellow & gray clay & few rock ledges.	
	164		174	Sand fine to medium coarse. Small gravel.	
	174		181	Brown, yellow & gray clay.	
	181		213	Sand fine to medium coarse, Small gravel & few medium gravel.	
	213		239	Brown & yellow clay.	
	239		244	Sand fine to medium coarse.	
	244		275	Brown clay & very few Limerock ledges.	
	275		294	Brown & Gray clay.	
	294		302	Clay & sand streaks.	
	302		330	Sand fine to medium coarse & few clay streaks.	
60	330	30	360	Sand fine to medium coarse. Small & few medium gravel & very few clay streaks, (Drilled loose & rough in places).	
70	360	36	396	Sand fine to medium coarse. Small to medium gravel & few clay streaks (Drills a little rough) some cemented ledges.	
	396		400	Brown clay.	
70	400	18	418	Sand fine to medium coarse, Small to medium gravel & few cemented ledges & few clay streaks.	
	418		460	Brown clay & limerock ledges.	
	460		498	Brown sandy clay & fine sand.	
70	498	7	505	Sand fine to medium coarse. Brown rock & gravel.	
	505		508	Brown clay.	
75	508	11	519	Sand fine to medium coarse. Brown rock & gravel.	
	519		521	Brown clay.	
75	521	22	542	Sand fine to medium coarse. Brown rock & gravel.	
	542		549	Brown clay.	
30	549	13	562	Sand fine & sandstone.	
	562		567	Blue soapstone.	
25	567	33	600	Sandstone & soapstone.	
30	600	5	605	Sandstone.	
	605		635	Soapstone & Limestone.	

GARDEN CITY, KS 67846
 3795 West Jones Ave.

HENKLE DRILLING & SUPPLY CO., INC.

316-277-2389

IRRIGATION HEADQUARTERS

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS

