

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 041 HASKELL	Fraction NW 1/4 NE 1/4 SE 1/4	Section Number 34	Township Number T 29 S	Range Number R 34 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM SATANTA; APPX 2 MILES NORTH & 1 3/4 MILES WEST

2 WATER WELL OWNER: DANIEL B. STEPHENS
RR#, St. Address, Box # : 4611 50TH STREET
City, State, ZIP code : LUBBOCK, TX 79414-3521
Board of Agriculture, Division of Water Resources
Application Number: _____

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 422 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 12 1/4 in. to 422 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTHER CASING JNT CERTLOK
Blank casing diameter 6 in. to 405 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 6 in., weight 4 lbs/ft. Wall thickness or gauge No. .316
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS:	From 385 ft. to 405 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.
	From 40 ft. to 422 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? _____ How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	35	01 CLAY 04 SANDY CLAY			
35	60	09 COARSE SAND 15 CRS GRAVEL			
60	70	04 SANDY CLAY 11 GRAVEL			
70	100	09 COARSE SAND 15 CRS GRAVEL			
100	130	11 GRAVEL 09 COARSE SAND			
130	200	08 MEDIUM SAND 09 COARSE SAND 15 CRS GRAVEL			
200	225	01 CLAY 05 SAND			
225	250	05 SAND			
250	260	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/09/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/15/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	1/4 1/4 SW 1/4	34	T 29 S	R 34 W

2 WATER WELL OWNER: DANIEL B. STEPHENS
RR#, St. Address, Box # : 4611 50TH STREET
City, State, ZIP code : LUBBOCK, TX 79414-3521

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
260	390	08 MEDIUM SAND 09 COARSE SAND
390	400	01 CLAY 05 SAND
400	410	05 SAND
410	422	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/09/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/08/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Henkle*