

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

|  |                                  |                      |                           |                        |
|--|----------------------------------|----------------------|---------------------------|------------------------|
| 1 LOCATION OF WATER WELL:<br>COUNTY: 041 HASKELL | Fraction<br>SW 1/4 SW 1/4 NW 1/4 | Section Number<br>36 | Township Number<br>T 29 S | Range Number<br>R 34 W |
|--|----------------------------------|----------------------|---------------------------|------------------------|

Distance and direction from nearest town or city street address of well if located within city?  
FROM SUBLETTE; APPX 9 MILES WEST

2 WATER WELL OWNER: MARY CLAWSON TRUST  
RR#, St. Address, Box #: RT 1 BOX 65F  
City, State, ZIP code: SATANTA, KS 67870-9705  
Board of Agriculture, Division of Water Resources  
Application Number: 21945

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

|     |     |    |     |    |
|-----|-----|----|-----|----|
| / \ |     |    |     |    |
| 1   | --- | NW | --- | NE |
| M   | X   |    |     |    |
| i   | W   |    |     | E  |
| l   |     |    |     |    |
| e   |     |    |     |    |
|     |     | SW |     | SE |
| \ / |     |    |     |    |

4 DEPTH OF COMPLETED WELL 652 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 380 ft. below land surface measured on mo/day/yr 04/11/06  
Pump test data: Well water was 503 ft. after 4 hours pumping 443 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 652 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
Blank casing diameter 16 in. to 652 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

|                              |                          |                     |
|------------------------------|--------------------------|---------------------|
| SCREEN PERFORATED INTERVALS: | From 457 ft. to 647 ft., | From 0 ft. to 0 ft. |
|                              | From 0 ft. to 0 ft.,     | From 0 ft. to 0 ft. |
| GRAVEL PACK INTERVALS:       | From 20 ft. to 652 ft.,  | From 0 ft. to 0 ft. |
|                              | From 0 ft. to 0 ft.,     | From 0 ft. to 0 ft. |

6 GROUT MATERIAL 03 BENTONITE  
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: 14 ABAND. WELL  
Direction from well? SOUTHWEST How many feet? 201

| FROM | TO  | LITHOLOGIC LOG                          | FROM | TO | PLUGGING INTERVALS |
|------|-----|---|------|----|--------------------|
| 0    | 2   | 02 SILT                                 |      |    |                    |
| 2    | 47  | 04 SANDY CLAY 20 LIMESTONE 07 FINE SAND |      |    |                    |
| 47   | 86  | 05 SAND 11 GRAVEL                       |      |    |                    |
| 86   | 95  | 04 SANDY CLAY                           |      |    |                    |
| 95   | 104 | 05 SAND 11 GRAVEL                       |      |    |                    |
| 104  | 108 | 04 SANDY CLAY                           |      |    |                    |
| 108  | 186 | 05 SAND 11 GRAVEL 01 CLAY               |      |    |                    |
| 186  | 235 | 04 SANDY CLAY 01 CLAY                   |      |    |                    |
| 235  | 250 | 05 SAND                                 |      |    |                    |
| 250  | 253 | 01 CLAY                                 |      |    |                    |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/06/06 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

|  |                                  |                      |                           |                        |
|--|----------------------------------|----------------------|---------------------------|------------------------|
| 1 LOCATION OF WATER WELL:<br>COUNTY: 041 HASKELL | Fraction<br>SW 1/4 SW 1/4 NW 1/4 | Section Number<br>36 | Township Number<br>T 29 S | Range Number<br>R 34 W |
|--|----------------------------------|----------------------|---------------------------|------------------------|

|   |  |  |
|---|--|--|
| 2 WATER WELL OWNER:<br>RR#, St. Address, Box # :<br>City, State, ZIP code : | MARY CLAWSON TRUST<br>RT 1 BOX 65F<br>SATANTA, KS 67870-9705 | Board of Agriculture, Division of Water Resources<br>Application Number: 21945 |
|---|--|--|

| FROM | TO  | LITHOLOGIC LOG                     |
|------|-----|------------------------------------|
| 253  | 363 | 05 SAND 13 FINE GRAVEL 01 CLAY     |
| 363  | 397 | 04 SANDY CLAY 05 SAND              |
| 397  | 408 | 05 SAND                            |
| 408  | 456 | 04 SANDY CLAY 05 SAND 20 LIMESTONE |
| 456  | 497 | 07 FINE SAND                       |
| 497  | 509 | 05 SAND 28 ROCK                    |
| 509  | 516 | 04 SANDY CLAY                      |
| 516  | 530 | 07 FINE SAND 01 CLAY               |
| 530  | 532 | 05 SAND 28 ROCK                    |
| 532  | 544 | 04 SANDY CLAY 07 FINE SAND         |
| 544  | 550 | 31 CALICHE 19 SHALE                |
| 550  | 560 | 23 SANDSTONE                       |
| 560  | 567 | 31 CALICHE                         |
| 567  | 590 | 23 SANDSTONE                       |
| 590  | 603 | 31 CALICHE 23 SANDSTONE            |
| 603  | 697 | 23 SANDSTONE 31 CALICHE            |
| 697  | 650 | 19 SHALE                           |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/06/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

*Bernie Reichert*