

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SW 1/4 SE 1/4	06	T 29 S	R 34 W

Distance and direction from nearest town or city street address of well if located within city?

FROM SATANTA; APPX 7 MILES NORTH & 4 MILES WEST2 WATER WELL OWNER: **KENBY CLAWSON**RR#, St. Address, Box # : **146 140TH ROAD**

Board of Agriculture, Division of Water Resources

City, State, ZIP code : **SATANTA, KS 67870-8400**

Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:4 DEPTH OF COMPLETED WELL **660**ELEVATION: **0**

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \				
1	--- NW ---	---	NE ---	
M				
i W	---	---	---	E
l				
e				
	--- SW ---	---	SE ---	
/ \				
---	---	---	---	---

WELL'S STATIC WATER LEVEL **362** ft. below land surface measured on mo/day/yr **09/13/06**

Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter **12 1/4** in. to **660** ft., and in. to 0 ft.WELL WATER TO BE USED AS: **01 DOMESTIC**Was a chemical/bacteriological sample submitted to department? **No** ;If yes, mo/day/yr sample was submitted Water well disinfected? **Yes**5 TYPE OF BLANK CASING USED: **02 PVC**CASING JOINTS: **OTHER - CERTI LOCK**Blank casing diameter **5** in. to **660** ft., Dia in. to 0 ft., Dia in. to 0 ft.Casing height above land surface **12** in., weight **4** lbs/ft. Wall thickness or gauge No. **.327**TYPE OF SCREEN OR PERFORATION MATERIAL: **07 PVC**SCREEN OR PERFORATION OPENINGS ARE: **03 MILL SLOT**SCREEN PERFORATED INTERVALS: From **460** ft. to **500** ft., From 0 ft. to 0 ft.From **580** ft. to **660** ft., From 0 ft. to 0 ft.GRAVEL PACK INTERVALS: From **25** ft. to **660** ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL **03 BENTONITE**Grout Intervals: From **5** ft. to **25** ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.What is the nearest source of possible contamination: **NONE OBSERVED**Direction from well? How many feet? **0**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	02 SILT			
4	56	01 CLAY 31 CALICHE 05 SAND			
56	82	05 SAND 11 GRAVEL			
82	98	01 CLAY 05 SAND			
98	219	05 SAND 11 GRAVEL			
219	225	01 CLAY			
225	243	05 SAND 13 FINE GRAVEL 01 CLAY			
243	256	01 CLAY 05 SAND			
256	280	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
280	320	05 SAND 13 FINE GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **06/23/06** and this record is true to the best of my knowledge and belief. KansasWater Well Contractor's License No. **145**This Water Well Record was completed on (mo/day/yr) **11/08/06**under the business name of **HENKLE DRILLING & SUPPLY**

by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SW 1/4 SE 1/4	06	T 29 S	R 34 W

2 WATER WELL OWNER: KENBY CLAWSON

RR#, St. Address, Box # : 146 140TH ROAD

City, State, ZIP code : SATANTA, KS 67870-8400

Board of Agriculture, Division of Water Resources

Application Number:

FROM	TO	LITHOLOGIC LOG
320	356	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
356	364	01 CLAY 05 SAND
364	379	05 SAND 13 FINE GRAVEL 01 CLAY
379	398	01 CLAY 20 LIMESTONE 05 SAND
398	408	07 FINE SAND 08 MEDIUM SAND 01 CLAY
408	425	01 CLAY 20 LIMESTONE 05 SAND
425	435	01 CLAY 20 LIMESTONE
435	472	01 CLAY 20 LIMESTONE 05 SAND
472	480	07 FINE SAND 08 MEDIUM SAND 01 CLAY
480	522	05 SAND 28 ROCK 13 FINE GRAVEL
522	536	01 CLAY
536	553	01 CLAY 19 SHALE
553	564	19 SHALE 01 CLAY 23 SANDSTONE
564	585	31 CALICHE 19 SHALE
585	600	31 CALICHE
600	620	01 CLAY
620	655	01 CLAY
655	660	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/23/06 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 11/08/06

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

