

WATER WELL RECORD Form #WC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 034 GRANT | SW 1/4 NW 1/4 SW 1/4 | 01 | T 29 S | R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 4 MILES NORTH OF RYUS

2 WATER WELL OWNER: D. MILLER %GARRY ANTHONY
 RR#, St. Address, Box #: RFD #1 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SATANTA, KS 67870- Application Number: 11,741

3 LOCATE WELL'S LOCATION WITH | 4 DEPTH OF COMPLETED WELL: 660 ELEVATION: 0
 AN "X" IN SECTION BOX: | Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 325 ft. below land surface measured on mo/day/yr 06/12/95
 Pump testdata: Well water was 415 ft. after 4 hours pumping 1095 gpm
 Estimated Yield 1095 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 660 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 660 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .25
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 360 ft. to 660 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 660 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	6	04 SANDY CLAY			
6	15	07 FINE SAND			
15	32	04 SANDY CLAY			
32	35	01 CLAY 04 SANDY CLAY			
35	44	04 SANDY CLAY			
44	70	09 COARSE SAND 11 GRAVEL			
70	74	04 SANDY CLAY 20 LIMESTONE			
74	81	01 CLAY			
81	156	05 SAND 11 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 06/08/95 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/16/95
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

