

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT	SE 1/4 SE 1/4 SW 1/4	13	T 29 S	R 35 W

Distance and direction from nearest town or city street address of well if located within city?

FROM RYUS; APPX 1 3/4 MILES NORTH

2 WATER WELL OWNER:	ROONEY AGRI BUSINESS
RR#, St. Address, Box # :	RR 1 BOX 2
City, State, ZIP code :	SATANTA, KS 67870-
	Board of Agriculture, Division of Water Resources
	Application Number: 7704

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 621	ELEVATION: 0
	Depth(s) Groundwater Encountered	1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \	WELL'S STATIC WATER LEVEL 374 ft. below land surface measured on mo/day/yr 09/26/07
	Pump test data: Well water was 424 ft. after 4 hours pumping 842 gpm

1	Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
---	---

M	Bore Hole Diameter 24 in. to 621 ft., and in. to 0 ft.
---	--

1	WELL WATER TO BE USED AS: 02 IRRIGATION
---	---

e	Was a chemical/bacteriological sample submitted to department? No ;
\ /	If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
Blank casing diameter 16 in. to 621 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250	
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL	
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT	

SCREEN PERFORATED INTERVALS:	From 388 ft. to 538 ft., From 0 ft. to 0 ft.
	From 556 ft. to 616 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 621 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? SOUTHEAST
How many feet? 209

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	26	07 FINE SAND 01 CLAY			
26	60	04 SANDY CLAY 07 FINE SAND			
60	79	07 FINE SAND 08 MEDIUM SAND			
79	95	05 SAND 11 GRAVEL			
95	120	01 CLAY 20 LIMESTONE			
120	181	05 SAND 11 GRAVEL 28 ROCK			
181	203	01 CLAY 20 LIMESTONE			
203	240	07 FINE SAND 01 CLAY			
240	380	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/21/07 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/19/07
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT	SE 1/4 SE 1/4 SW 1/4	13	T 29 S	R 35 W

2 WATER WELL OWNER: ROONEY AGRI BUSINESS

RR#, St. Address, Box # : RR 1 BOX 2

Board of Agriculture, Division of Water Resources

City, State, ZIP code : SATANTA, KS 67870-

Application Number: 7704

FROM	TO	LITHOLOGIC LOG
380	403	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
403	416	07 FINE SAND 08 MEDIUM SAND
416	432	01 CLAY
432	488	07 FINE SAND 01 CLAY
488	498	23 SANDSTONE
498	538	31 CALICHE 23 SANDSTONE
538	550	19 SHALE 31 CALICHE
550	561	31 CALICHE
561	616	31 CALICHE 23 SANDSTONE
616	630	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/21/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 10/19/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

