

The
Professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67840

August 15, 1977

Glenn Jarvis
Grant County

Location: NE $\frac{1}{4}$ 23-29-36 $\frac{1}{2}$ Mile South of Wagon Bed Inn, $\frac{3}{4}$
mile East, $\frac{1}{2}$ North

Static Water Level - 270

Test #1

0	1	Top Soil
1	203	Brown Clay
203	270	Blue Clay
270	312	Fine to med. sand and gravel (loose)
312	320	Brown Clay small streaks of gravel 30% (loose)
320	338	Brown Clay
338	350	Brown Sandy Clay
350	365	Brown Sandy Clay streaks of gravel 35% (loose)
365	397	Brown Sandy Clay 20% Gravel (loose)
397	425	Brown Sandy Clay
425	493	Fine to med. sand and gravel 10% Clay (loose)
493	503	Fine to med. sand and gravel 35% Clay (Fairly loose)
503	515	Brown Gray & Yellow Clay small streaks of gravel 20% (Fairly loose)
515	534	Brown Gray & Yellow Clay (tight) (Hard streaks)
534	545	Brown Gray Yellow & Red Clay (hard)

T. D. 515'