

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON LOT 4 1/4 NW 1/4 NW 1/4 06 T 29 S R 39 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM BIG BOW; APPX 3 3/4 MILES WEST

2 WATER WELL OWNER: EMJ FARMS
 RR#, St. Address, Box # : 1737 S. ROAD F Board of Agriculture, Division of Water Resources
 City, State, ZIP code : JOHNSON, KS 67855- Application Number: 17102, 8240, 4814, 3351

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 561 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 309 ft. below land surface measured on mo/day/yr 11/24/07
 Pump test data: Well water was 355 ft. after 4 hours pumping 1474 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 561 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 561 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 370 ft. to 420 ft., From 0 ft. to 0 ft.
 From 446 ft. to 556 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 561 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 196

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	23	03 SILTY CLAY			
23	35	05 SAND 13 FINE GRAVEL			
35	56	01 CLAY 05 SAND			
56	70	05 SAND 13 FINE GRAVEL			
70	94	01 CLAY 05 SAND			
94	138	01 CLAY 05 SAND			
138	164	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
164	180	01 CLAY 05 SAND			
180	204	07 FINE SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/20/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/03/08 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 094 STANTON	LOT 4 1/4 NW 1/4 NW 1/4	06	T 29 S	R 39 W

2 WATER WELL OWNER:	EMJ FARMS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	1737 S. ROAD F	Application Number: 17102, 8240,
City, State, ZIP code :	JOHNSON, KS 67855-	

FROM	TO	LITHOLOGIC LOG
204	220	01 CLAY
220	240	07 FINE SAND 08 MEDIUM SAND
240	285	05 SAND
285	300	01 CLAY 05 SAND
300	325	05 SAND
325	340	01 CLAY
340	364	06 VERY FN SAND 01 CLAY
364	375	05 SAND 28 ROCK
375	420	05 SAND 13 FINE GRAVEL 28 ROCK
420	426	20 LIMESTONE
426	440	31 CALICHE 19 SHALE 20 LIMESTONE
440	477	31 CALICHE 23 SANDSTONE
477	482	19 SHALE
482	500	31 CALICHE 23 SANDSTONE
500	530	31 CALICHE 23 SANDSTONE
530	556	31 CALICHE 23 SANDSTONE
556	572	31 CALICHE 20 LIMESTONE 19 SHALE
572	585	19 SHALE 31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/20/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/03/08 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Reichert