

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County SEDGWICK	Fraction 1/4 SW 1/4 SE 1/4	Section number 10	Township number T 29 S	Range number R 4W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city:		3. Owner of well: R.R. or street: City, state, zip code:			
1 3/4 East of 375th West on 87th South, then		Albert Olthoff Route #1 Milton, Kansas			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile NW NE SW SE X		Sketch map: 1/4 North on west side of rd. Cheney, Kansas			
5. Type and color of material		From	To	6. Bore hole dia. 11 in. Completion date 5-10-78 Well depth 65 ft.	
Sandy Topsoil		0	4	7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Red Clay		4	10	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Red Shale		10	65	9. Casing: Material styrene Height: Above or below surface 12 in. Threaded ☐ Welded ☒ RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 65 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 200	
				10. Screens: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot/gauge 1/4" .06 Length 45' Set between 20 ft. and 65 ft. Set between ☐ ft. and ☐ ft. Gravel pack? yes Size range of material 1/2-1/8"	
				11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 5-10-78	
				12. Pumping level below land surfaces: ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
				13. Water sample submitted: ☐ Yes ☐ No Date ☐	
				14. Well head completion: capped ☐ Pitless adapter 12 inches above grade	
				15. Well grouted? yes 1-2 fine sand mix With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.	
				16. Nearest source of possible contamination: Septic Tank ft. 60 Direction WEST Type Tank Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)					
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: Flat Ground			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas 67209 Signed M. Arnold Date 5-31-78 Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5