

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 094 STANTON	Fraction SW 1/4 SE 1/4 NW 1/4	Section Number 04	Township Number T 29 S	Range Number R 40 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM JOHNSON; APPX 2 MILE EAST

2 WATER WELL OWNER: MELVIN WINGER
RR#, St. Address, Box # : PO BOX 914
City, State, ZIP code : JOHNSON, KS 67855-0914
Board of Agriculture, Division of Water Resources
Application Number: 25,776

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M	---		---	
i	W	X		E
l	---		---	
e	---	SW	---	SE
\ /				

4 DEPTH OF COMPLETED WELL 517 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 333 ft. below land surface measured on mo/day/yr 04/13/04
Pump test data: Well water was 365 ft. after 4 hours pumping 1100 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 517 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 517 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 352 ft. to 392 ft.,	From 0 ft. to 0 ft.
	From 392 ft. to 512 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 517 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	20	04 SANDY CLAY 31 CALICHE 07 FINE SAND			
20	30	01 CLAY			
30	43	01 CLAY			
43	54	01 CLAY			
54	68	05 SAND 13 FINE GRAVEL			
68	78	01 CLAY 05 SAND			
78	160	05 SAND 11 GRAVEL 01 CLAY			
160	177	01 CLAY 05 SAND			
177	212	05 SAND 01 CLAY 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/08/04 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/23/04
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 094 STANTON	Fraction SW 1/4 SE 1/4 NW 1/4	Section Number 04	Township Number T 29 S	Range Number R 40 W
--	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: MELVIN WINGER

RR#, St. Address, Box # : PO BOX 914

City, State, ZIP code : JOHNSON, KS 67855-0914

Board of Agriculture, Division of Water Resources *

Application Number: 25,776

FROM	TO	LITHOLOGIC LOG
212	219	01 CLAY
219	240	05 SAND 11 GRAVEL 28 ROCK
240	246	01 CLAY
246	257	05 SAND 11 GRAVEL 28 ROCK
257	273	01 CLAY 05 SAND
273	288	05 SAND 13 FINE GRAVEL
288	294	01 CLAY
294	384	05 SAND 11 GRAVEL 28 ROCK
384	390	05 SAND 01 CLAY
390	396	05 SAND
396	404	01 CLAY
404	424	07 FINE SAND 01 CLAY
424	434	07 FINE SAND 01 CLAY
434	444	01 CLAY
444	452	07 FINE SAND
452	460	01 CLAY
460	475	05 SAND 13 FINE GRAVEL 28 ROCK
475	482	01 CLAY
482	497	07 FINE SAND 08 MEDIUM SAND
497	512	31 CALICHE 23 SANDSTONE
512	525	31 CALICHE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/08/04 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/23/04

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruno J. Richman