

USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stanton	Fraction NE 1/4 NE 1/4 SW 1/4	Section number 34	Township number T 29 S	Range number R 40 E/W
2. Distance and direction from nearest town or city: 18 west, 7 south, 1/2 east, 1/2 north of Ulysses, Kansas Street address of well location if in city:				3. Owner of well: William H. Dye R.R. or street: % Robert Martin City, state, zip code: Johnson, Kansas		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile Sketch map:				6. Bore hole dia. 27 in. Completion date 9/2/76 Well depth 500 ft.		
5. Type and color of material				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☐ Domestic ☒ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Surface				9. Casing: Material Steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 36.8 lbs./ft. Dia. 16 in. to 240 ft. depth Wall thickness: inches or Dia. in. to ft. depth Gauge No. .219		
				10. Screen: Manufacturer's name Lakewood Pipe of Texas Type steel Dia. 16" Slot/gauze 3/16 Length 260' Set between 240 ft. and 500 ft. Gravel pack? ☒ Size range of material 1/4 X 5/8"		
Fine to medium sand				From 0	To 2	11. Static water level: 165 ft. below land surface Date 5/7/76
Sandy clay w/lime shale				2	76	12. Pumping level below land surfaces: 1200 ft. after 10 hrs. pumping 1200 g.p.m. 210 ft. after 18 hrs. pumping 1300 g.p.m. Estimated maximum yield 1300 g.p.m.
Fine to coarse sand w/sandy clay strips				76	133	13. Water sample submitted: No mo./day/yr.
Medium to coarse sand w/clay breakers (22')				133	173	14. Well head completion: NA ☐ Pitless adapter ☐ Inches above grade
Embedded sand w/fine loose strips (3')				173	252	15. Well grouted? ☒ With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
Very fine to coarse sand w/embedded sand (20')				252	259	16. Nearest source of possible contamination: NA ft. Direction Type Well disinfected upon completion? ☒ Yes ☐ No
Sandy clay, lime shells & very fine sand (13')				259	283	17. Pump: ☒ Not installed
Very fine to fine sand w/embedded sandstone (23')				283	313	Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
Brown shale, sandy clay & medium sand strips				313	342	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Houck Bros. Drlg. Co. 154 Business name License No. Address Box 487, Ulysses, Ks. Signed Mellie M. Beard Date 10/15/76 Authorized representative
Yellow chalk, brown shale & sandrock, Dakota 40%				342	353	
Yellow chalk, false red bed, Cheyenne, (Tight)				353	380	
Brown shale, yellow chalk, Cheyenne & Dakota 60%				380	390	
Brown shale, false red bed, Cheyenne & Dakota				390	441	
60%				441	500	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley						