

1 LOCATION OF WATER WELL: Fraction NW 1/4 NW 1/4 NW 1/4 Section Number 25 Township Number T 29 S Range Number R 41 W
 COUNTY: STANTION

Distance and direction from nearest town or city street address of well if located within city?
 FROM JOHNSON, KS. - 4 SOUTH ON HIGHWAY 27

2 WATER WELL OWNER: PISS, VERNON Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: P.O. BOX 100 Application Number:
 City, State, ZIP code: JOHNSON, KS 67855-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

X			
NW	NE		
SW	SE		

4 DEPTH OF COMPLETED WELL 413 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 262 ft. below land surface measured on no/day/yr 10/02/95
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 20 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 413 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 413 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 285 ft. to 325 ft., From 0 ft. to 0 ft.
 From 365 ft. to 408 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 413 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: WATERTIGHT SEW.
 Direction from well? NORTHWEST How many feet? 225

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	TOPSOIL CLAY FINE - MED SAND			
40	60	CLAY CALACHIE			
60	80	CLAY FINE SAND IN LAYERS			
80	120	FINE - MED SAND CLAY IN LAYERS			
120	140	CLAY FINE - MED SAND			
140	160	FINE SAND COARSE SAND SMALL GRAVEL			
160	200	FINE - MED SAND			
200	240	MED-COARSE SAND SMALL GRAVEL			
240	260	MED-COARSE SAND SMALL GRAVEL CLAY			
260	280	CLAY MEDIUM SAND SMALL GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 10/05/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 10/05/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joseph Crick*

(Continued)

1 LOCATION OF WATER WELL: Fraction NW 1/4 NW 1/4 NW 1/4 Section Number 25 Township Number T 29 S Range Number R 41 W
 COUNTY: STANTION

2 WATER WELL OWNER: PISS, VERNON Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: P.O. BOX 100 Application Number:
 City, State, ZIP code: JOHNSON, KS 67855-

FROM	TO	LITHOLOGIC LOG
280	300	MED-COARSE SAND CLAY
300	320	FINE - MED SAND CLAY THIN ROCK LAYER
320	335	FINE - MED SAND CLAY
335	365	BLUE SHALE
365	410	SANDSTONE
410	420	RED BED