

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTON SW 1/4 SE 1/4 SW 1/4 12 T 29 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM JOHNSON - SOUTH ON HIGHWAY 2 MILES AND 1/2 MILE EAST

2 WATER WELL OWNER: ARNOLD, EARL
 RR#, St. Address, Box #: 281 ERD 15 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JOHNSON, KS 67855- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 485 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 179 ft. below land surface measured on mo/day/yr 05/01/97
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 485 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 485 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 280 ft. to 300 ft., From 440 ft. to 480 ft.
 From 360 ft. to 400 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 35 ft. to 485 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? EAST How many feet? 300

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	CLAY			
40	60	CLAY FINE SAND IN LAYERS			
60	100	CLAY CALACHIE			
100	140	CLAY CALACHIE FINE SAND			
140	160	FINE SAND CLAY			
160	180	FINE SAND			
180	220	FINE - MED SAND			
220	240	CLAY MEDIUM SAND			
240	320	MED-COARSE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/02/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/23/97 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Cusick*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTON SW 1/4 SE 1/4 SW 1/4 12 T 29 S R 41 W

2 WATER WELL OWNER: ARNOLD, EARL
 RR#, St. Address, Box #: 281 ERD 15 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JOHNSON, KS 67855- Application Number:

FROM	TO	LITHOLOGIC LOG
320	340	FINE - MED SAND
340	360	CLAY MEDIUM SAND
360	380	MEDIUM SAND CLAY
380	400	MEDIUM SAND
400	420	CLAY FINE SAND
420	440	FINE - MED SAND
440	485	MEDIUM SAND
485	500	CLAY ROCK LAYERS