

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTION SW 1/4 SW 1/4 SE 1/4 23 T 29 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM JOHNSON - 4 SOUTH ON HIGHWAY 27 - 1/2 WEST

2 WATER WELL OWNER: WALKER, KIM
 RRR#, St. Address, Box #: 251 N. ROAD L Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JOHNSON, KS 67855- Application Number:

3 LOCATE WELL'S LOCATION WITH AN 'X' IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 507 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 274 ft. below land surface measured on no/day/yr 12/12/97
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 507 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 507 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 320 ft. to 340 ft., From 480 ft. to 500 ft.
 From 380 ft. to 460 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 35 ft. to 507 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	110	CLAY			
110	130	FINE - MED SAND SMALL GRAVEL			
130	145	CLAY			
145	160	FINE - MED SAND			
160	235	MED-COARSE SAND			
235	260	FINE - MED SAND CLAY LAYERS			
260	280	CLAY LAYERS FINE SAND COARSE SAND			
280	300	CLAY LAYERS FINE - MED SAND			
300	330	FINE - MED SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 12/13/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 12/30/97 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Josaid Creek*

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTION SW 1/4 SW 1/4 SE 1/4 23 T 29 S R 41 W

2 WATER WELL OWNER: WALKER, KIM
 RRR#, St. Address, Box #: 251 N. ROAD L Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JOHNSON, KS 67855- Application Number:

FROM	TO	LITHOLOGIC LOG
330	340	YELLOW CLAY THIN ROCK LAYER
340	360	YELLOW CLAY THIN ROCK LAYER BLUE SHALE
360	380	BLUE SHALE THIN ROCK LAYER
380	400	THIN ROCK LAYER SANDSTONE
400	460	SANDSTONE
460	510	SANDSTONE