

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTION SE 1/4 SE 1/4 NE 1/4 18 T 29 S R 42 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM MANTER WEST ON 160 HIGHWAY 1/4, 2 1/2 WEST & 1/2 NORTH

2 WATER WELL OWNER: WILKERSON, BILL
 RR#, St. Address, Box #: BOX 157 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: MANTER, KS 67862- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 423 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 223 ft. below land surface measured on mo/day/yr 07/22/05
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 423 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 423 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 198 ft. to 258 ft., From 0 ft. to 0 ft.
 From 358 ft. to 418 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 26 ft. to 423 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 5 ft. to 26 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 29 SANDSTONE			
20	40	29 SANDSTONE BROWN 27 ROCK			
40	60	27 ROCK 05 CLAY 29 SANDSTONE			
60	80	29 SANDSTONE 36 BLUE CLAY 31 SHALE			
80	100	31 SHALE 05 CLAY 29 SANDSTONE			
100	120	36 BLUE CLAY 16 GRAY CLAY			
120	140	16 GRAY CLAY 29 SANDSTONE 19 LAYERS			
140	160	16 GRAY CLAY 29 SANDSTONE			
160	200	29 SANDSTONE BROWN 27 ROCK			
200	255	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/23/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 07/29/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) Judith Crist

