

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTION SE 1/4 NW 1/4 SW 1/4 14 T 29 S R 42 W

Distance and direction from nearest town or city, street address of well if located within city?
 316 E. 1ST AVE. HANTER, KS 67862- *midway between ASW-4 and RmW-4 Calloway Basin*

2 WATER WELL OWNER: SKYLAND GRAIN, LLC. *ASW-5*
 RRR, St. Address, Box #: 304 HIGHLAND AVE. Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JOHNSON, KS 67855- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 90 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on no/day/yr 09/03/10
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpa
 Estimated Yield 0 gpa: Well water was 0 ft. after 0 hours pumping 0 gpa
 Bore Hole Diameter 6.25 in. to 95 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: MONITORING
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: THREADED
 Blank casing diameter 2 in. to 90 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No.
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 84 ft. to 90 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 80 ft. to 95 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 80 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: FUEL STORAGE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	01 TOPSOIL 09 GRAVEL			
4	10	05 CLAY			
10	20	05 CLAY			
20	32	05 CLAY 35 CALACHIE 19 LAYERS			
32	46	05 CLAY			
46	55	05 CLAY 35 CALACHIE			
55	70	28 SAND 35 CALACHIE			
70	80	28 SAND 09 GRAVEL			
80	84	28 SAND 06 SHALL GRAVEL			
84	95	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 09/03/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 10/05/10 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Justin Crick*