

DRILLERS TEST LOG

CUSTOMERS NAME Milton Graber DATE 3-4-75
 STREET ADDRESS _____ TEST # 1
 CITY & STATE Manter, Kansas DRILLER Livingston
 COUNTY Stanton QUARTER NE SECTION 26 TOWNSHIP 29 RANGE 42

LOCATION 450 Ft. North of the SE corner of the NW 1/4
Camp drilling Co. drilled 30 Ft. SW and 50 Ft. NW.

WELL LOCATION.

%	DRILLED FOOTAGE		Description of Strata	Static Water Level
	from	Pay to		Proposed Well Depth
	0		2	Top soil
	2		30	Brown clay, caliche and few sand st.
	30		54	Sand fine to med.
	54		200	Soapstone, sandstone, firm. Used pulldown. Lost circulation at 168'
Good	200	47	267	White sandstone. Used water.
	267		345	Weathered shale
	345		350	Limestone, shale, hard.
Good	350	20	370	White Dakota. Lost circulation
Fair	370	30	400	Dakota and shale. Firm
	400		430	Red shale and limestone and few Dakota st. Hard.
Good	430	80	510	White Dakota. Drills loose in places.
	510		512	Red shale
Good	512	25	537	White Dakota. Loose in places.
	537		540	Limestone. Hard.
TOTAL DEPTH OF WELL 539 Ft.				
Set up south. Dig pit on the west.				
11 Sacks Bran 2 Sacks Revert 6 Sacks Quick Jel 1 10 lb. line 14 Loads of water.				