

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: STANTON NE 1/4 NW 1/4 NW 1/4 29 T 29 S R 43 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SAUNDERS - 2 1/2 MILES ON STATE LINE ROAD

2 WATER WELL OWNER: HEBBERD, HADDEN
 REF, St. Address, Box #: BOX 116 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: MANTER, KS 67862- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 365 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \	X		
1	NW	NE	
M			
i	W	E	
l			
e	SW	SE	
\ /			

WELL'S STATIC WATER LEVEL 113 ft. below land surface measured on mo/day/yr 05/22/06
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 365 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 365 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 180 ft., From 0 ft. to 0 ft.
 From 280 ft. to 360 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 365 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY			
20	50	05 CLAY 10 FINE-MEDSAND			
50	80	05 CLAY BROWN 08 ROCK LAYERS			
80	100	16 GRAY CLAY 08 ROCK LAYERS 16 GRAY CLAY			
100	120	16 GRAY CLAY 36 BLUE CLAY 29 SANDSTONE			
120	140	16 GRAY CLAY 29 SANDSTONE			
140	180	40 TAN SANDSTON			
180	240	16 GRAY CLAY 07 BLUE SHALE			
240	260	16 GRAY CLAY 07 BLUE SHALE 29 SANDSTONE			
260	300	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/23/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/25/06 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joel Cook*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: STANTION	NE 1/4 NW 1/4 NW 1/4	29	T 29 S	R 43 W

2 WATER WELL OWNER: HEBBERD, HADDEM
RR#, St. Address, Box #: BOX 116 Board of Agriculture, Division of Water Resources
City, State, ZIP code: MANTER, KS 67862- Application Number:

FROM	TO	LITHOLOGIC LOG
300	380	WHITE RED 29 SANDSTONE
320	380	

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/23/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/25/06 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Creek*