


1 LOCATION OF WATER WELL: County: Kingman	Fraction NE 1/4 NE 1/4 NE 1/4	Section Number 29	Township Number T 29 S	Range Number R 5 ESW
---	---	-----------------------------	----------------------------------	--------------------------------

Distance and direction from nearest town or city street address of well if located within city?

3 MILES NORTH 2 MILES WEST of Norwich, Kansas

2 WATER WELL OWNER: Arland Stephens RR#, St. Address, Box # : City, State, ZIP Code : Norwich, Kansas, 67118	Board of Agriculture, Division of Water Resources Application Number:
--	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL: 80' ft. ELEVATION: Depth(s) Groundwater Encountered 1. 26' ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 26' ft. below land surface measured on mo/day/yr May 20-85 Pump test data: Well water was 72' ft. after 1hr hours pumping 20 gpm Est. Yield 20 gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 1/4" in. to 80' ft., and in. to ft. WELL WATER TO BE USED AS: ☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes No xxx ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes xx No
--	---

5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) xx PVC 4 ABS Blank casing diameter 5" in. to 55" ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 17" in., weight SR26--160 lbs./ft. Wall thickness or gauge No. SDR 26	5 Wrought iron 8 Concrete tile CASING JOINTS: Glued xxx Clamped 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Threaded
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)	
SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped xx Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 55' ft. to 80' ft., From ft. to ft. From ft. to ft., From ft. to ft.	
GRAVEL PACK INTERVALS: From ft. to ft., From ft. to ft. From 15' ft. to 80' ft., From ft. to ft.	

6 GROUT MATERIAL: xx 1 Neat cement 2 Cement grout 3 Bentonite 4 Other	
Grout Intervals: From 3 ft. to 15 ft., From ft. to ft., From ft. to ft.	
What is the nearest source of possible contamination: xx 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage	
Direction from well? South WEST How many feet? APP. 85'	

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	5	Sandy top soil			
5'	11'	brown clay.			
11'	17'	sandy clay.			
17'	24'	Fine sand.			
24'	32'	Course sand & fine gravel.			
32'	80'	Red bed w/ breaks of granular red bed.			
		42' 45' granular			
		62'- 66' granular.			
		76'- 79' granular			
		I think this formation produces water .			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) May 8- 1985 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 112 This Water Well Record was completed on (mo/day/yr) May 29-85 under the business name of Wells Drilling Co. by (signature) <i>Arland Stephens</i>

INSTRUCTIONS: Use typewriter or ball point pen, **PLEASE PRESS FIRMLY** and **PRINT** clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.