

1 LOCATION OF WATER WELL: County: Kingman		Fraction Near Center ☒ NE 1/4		Section Number 5		Township Number T 29 S		Range Number R 7 EW									
Distance and direction from nearest town or city street address of well if located within city? 6 miles south, 1/2 mi. West. of Kingman, Kns.																	
2 WATER WELL OWNER: Larry D. Woodson																	
RR#, St. Address, Box #: 109 SW9th ST. Room 100						Board of Agriculture, Division of Water Resources											
City, State, ZIP Code: Topeka, Kansas 66612-1272						Application Number: 39,227											
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:				4 DEPTH OF COMPLETED WELL: 144' ft. ELEVATION: 44' ft.													
				Depth(s) Groundwater Encountered 1. 44' ft. 2. _____ ft. 3. _____ ft.													
				WELL'S STATIC WATER LEVEL 44' ft. below land surface measured on mo/day/yr May 12-89													
				Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm													
				Est. Yield 1400 gpm: Well water was 72 ft. after 3 hours pumping _____ gpm													
				Bore Hole Diameter 28" in. to 144' ft., and _____ in. to _____ ft.													
WELL WATER TO BE USED AS:				5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) ☒ Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well													
Was a chemical/bacteriological sample submitted to Department? Yes _____ No XX _____; If yes, mo/day/yr sample was submitted _____																	
Water Well Disinfected? Yes _____ No _____																	
5 TYPE OF BLANK CASING USED:																	
1 Steel		3 RMP (SR)		5 Wrought iron		8 Concrete tile		CASING JOINTS: Glued _____ Clamped _____									
2 PVC		4 ABS		6 Asbestos-Cement		9 Other (specify below)		Welded XX _____									
				7 Fiberglass				Threaded _____									
Blank casing diameter 16" in. to 85' ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.																	
Casing height above land surface 12" in., weight 31.50 lbs./ft. Wall thickness or gauge No. 7																	
TYPE OF SCREEN OR PERFORATION MATERIAL:																	
XX 1 Steel		3 Stainless steel		5 Fiberglass		7 PVC		10 Asbestos-cement									
2 Brass		4 Galvanized steel		6 Concrete tile		8 RMP (SR)		11 Other (specify) _____									
						9 ABS		12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:																	
1 Continuous slot		3 Mill slot		5 Gauzed wrapped		8 Saw cut		11 None (open hole)									
XX 2 Louvered shutter		4 Key punched		6 Wire wrapped		9 Drilled holes											
				7 Torch cut		10 Other (specify) _____											
SCREEN-PERFORATED INTERVALS: From 85' ft. to 144' ft., From _____ ft. to _____ ft.																	
GRAVEL PACK INTERVALS: From _____ ft. to _____ ft., From _____ ft. to _____ ft.																	
From 144' ft. to 17' ft., From _____ ft. to _____ ft.																	
6 GROUT MATERIAL: XX 1 Neat cement 2 Cement grout 3 Bentonite 4 Other _____																	
Grout Intervals: From _____ ft. to _____ ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.																	
What is the nearest source of possible contamination:																	
1 Septic tank		4 Lateral lines		7 Pit privy		10 Livestock pens		14 Abandoned water well									
2 Sewer lines		5 Cess pool		8 Sewage lagoon		11 Fuel storage		15 Oil well/Gas well									
3 Watertight sewer lines		6 Seepage pit		XX 9 Feedyard		12 Fertilizer storage		16 Other (specify below)									
13 Insecticide storage _____																	
Direction from well? North How many feet? 1600'																	
FROM			TO			LITHOLOGIC LOG			FROM			TO			PLUGGING INTERVALS		
0'			15'			Top soil & clay.											
15'			20'			Fine sand.											
20'			30'			Course sand.											
30'			35'			Clay.											
35'			42'			Course sand.											
42'			52'			Course sand & Fine gravel/											
52'			56'			Clay.											
56'			60'			Good clean sand & Fine gravel.											
60'			80'			Medium Course sand.											
80'			90'			Course sand & fine gravel.											
90'			95'			Course sand & fine gravel.											
95'			96'			Clay.											
96'			145'			Fine sand (Very round & white).											
						Red bed.											

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **May 12--1989** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **112** This Water Well Record was completed on (mo/day/yr) **May 30--89** under the business name of **Wells Drilling Co.** by (signature) *Dal Wells*