


1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number			
County: <u>Kingman</u>		C 1/4 NW 1/4 SE 1/4		17		T 30 S		R 10 <u>EW</u>			
Distance and direction from nearest town or city street address of well if located within city? <u>1/4 west, 1/8 south of Nashville, Ks.</u>											
2 WATER WELL OWNER:		R & B Oil & Gas									
RR#, St. Address, Box # :		Box 195									
City, State, ZIP Code :		Attica, Ks. 67009-0195									
Board of Agriculture, Division of Water Resources Application Number: <u>970051</u>											
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>105</u> ft. ELEVATION:									
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.									
		WELL'S STATIC WATER LEVEL .. <u>45</u> ft. below land surface measured on mo/day/yr <u>2-5-97</u>									
		Pump test data: Well water was ft. after hours pumping gpm									
		Est. Yield na gpm: Well water was ft. after hours pumping gpm									
		Bore Hole Diameter ... <u>9 7/8</u> to <u>105</u> ft., and in. to ft.									
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well											
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)											
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well											
Was a chemical/bacteriological sample submitted to Department? Yes.....No... <u>X</u>; If yes, mo/day/yr sample was submitted											
Water Well Disinfected? Yes No <u>X</u>											
5 TYPE OF BLANK CASING USED:											
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued <u>X</u> Clamped											
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded											
7 Fiberglass Threaded											
Blank casing diameter ... <u>5</u> in. to <u>85</u> ft., Dia. in. to ft., Dia. in. to ft.											
Casing height above land surface ... <u>2</u> in., weight ... SDR <u>26</u> lbs./ft. Wall thickness or gauge No.											
TYPE OF SCREEN OR PERFORATION MATERIAL:											
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement											
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)											
12 None used (open hole)											
SCREEN OR PERFORATION OPENINGS ARE:											
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)											
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes											
7 Torch cut 10 Other (specify)											
SCREEN-PERFORATED INTERVALS: From ... <u>105</u> ft. to ... <u>85</u> ft., From ft. to ft.											
From ft. to ft., From ft. to ft.											
GRAVEL PACK INTERVALS: From ... <u>105</u> ft. to ... <u>20</u> ft., From ft. to ft.											
From ft. to ft., From ft. to ft.											
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other hole plug											
Grout Intervals: From ... <u>20</u> ft. to ... <u>0</u> ft., From ft. to ft., From ft. to ft.											
What is the nearest source of possible contamination:											
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well											
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well											
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)											
13 Insecticide storage											
Direction from well? <u>west</u> How many feet? <u>100</u>											
FROM		TO		LITHOLOGIC LOG		FROM		TO		PLUGGING INTERVALS	
0		3		Sandy top soil							
3		5		Brown & gray clay							
5		8		Tan clay							
8		18		White clay & rock							
18		23		Sand and gravel							
23		30		White clay							
30		36		Sandy brown clay							
36		43		Sandy white clay							
43		55		Sand and gravel							
55		62		Sandy brown clay							
62		77		Sand and gravel							
77		83		Brown clay							
83		105		Sand and gravel							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) ... <u>2-5-97</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. ... <u>134</u> This Water Well Record was completed on (mo/day/yr) ... <u>2-11-97</u> under the business name of <u>Rosencrantz-Bemis</u> by (signature) <u>Judith Jackson</u>											