

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: ; Fraction ; Section Number ; Township Number ; Range Number
 COUNTY: 049 KIOWA ; NE 1/4 SW 1/4 NE 1/4 ; 28 ; T 30 S ; R 20 W

Distance and direction from nearest town or city street address of well if located within city?
 2 1/2 W, 12 1/2 S. OF MULLINVILLE, KS.

2 WATER WELL OWNER: HUCK RANCH 077
 RR#, St. Address, Box #: BOX 43 RR.1 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: COLDWATER, KS 67029- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: ; 4 DEPTH OF COMPLETED WELL 116 ELEVATION:
 Depth(s) Groundwater Encountered 1. 62 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 62 ft. below land surface measured on mo/day/yr 8 /15/91
 Pump testdata: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 116 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 96 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 96 ft. to 116 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 116 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: CATTLE PASTURE
 Direction from well? ALL How many feet? 4

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	SILT & SAND			
3	14	05 SAND AND 17 GRAVEL			
14	64	TAN CLAY			
64	103	05 SAND AND 17 GRAVEL			
103	114	SANDSTONE			
114	116	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 8/15/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 08/24/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse