

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

MT. JESUS  
NW

A A B

1. Location of well:	County <b>Clark</b>	Fraction <b>NW 1/4 NE 1/4 NE 1/4</b>	Section number <b>4</b>	Township number <b>T 30 S R 22 E/W</b>	Range number <b>22</b>
2. Distance and direction from nearest town or city: <b>3 miles south, 2 miles east of Kingsdown, Ks.</b>			3. Owner of well: <b>Joe Baldwin</b> R.R. or street: <b>R.R.</b> City, state, zip code: <b>Kingsdown, Kansas</b>		
4. Locate with "X" in section below: <div style="display: flex; align-items: center;"><div style="text-align: center;"><p>N</p><p>1029' W of NE corner of the NE 1/4, Sec. 4, T30S, R22W, Clark Co., Kansas.</p></div><div style="margin-left: 20px;">Sketch map:</div></div>			6. Bore hole dia. <b>28</b> in. Completion date <b>9-30-76</b> Well depth <b>170</b> ft.		
5. Type and color of material			7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Top soil			8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Tan clay			9. Casing: Material <b>Stl.</b> Height: <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia. <b>16</b> in. to <b>110</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>.219</b>		
Cemented sand			10. Screen: Manufacturer's name <b>Cook</b>		
Tan clay			Type <b>Wirewrap</b> Dia. <b>16</b> Slot/gauze <b>1/8"</b> Length <b>60'</b> Set between <b>110</b> ft. and <b>170</b> ft. ft. and ft. Gravel pack? <b>Yes</b> Size range of material <b>4.4mm</b>		
Fine to coarse sand fine gravel			11. Static water level: <b>90</b> ft. below land surface Date <b>8-18-76</b>		
Black shale			12. Pumping level below land surfaces: <b>145</b> ft. after <b>1 1/2</b> hrs. pumping <b>713</b> g.p.m. <b>140</b> ft. after <b>1</b> hrs. pumping <b>727</b> g.p.m. Estimated maximum yield <b>700</b> g.p.m.		
			13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date		
			14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade		
			15. Well grouted? <b>Yes</b> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.		
			16. Nearest source of possible contamination: <b>unk</b> ft. Direction Type Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
			17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Layne &amp; Bowler</b> Model number <b>12 KEL</b> HP <b>70</b> Volts Length of drop pipe <b>160</b> ft. capacity <b>600</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne-Western Co., Inc. 10</b> Business name License No. Address <b>Garden City, Kansas</b> Signed <b>[Signature]</b> Date <b>18 Nov 76</b> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-3