

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
COUNTY: CLARK NE 1/4 NE 1/4 SE 1/4 32 T 30 S R 23 W

Distance and direction from nearest town or city street address of well if located within city?  
6.5 MILES SOUTH, 2 MILES EAST OF BLOOM

2 WATER WELL OWNER: GARRISON, KAREN  
RR#, St. Address, Box # : HCR 1 BOX 131 Board of Agriculture, Division of Water Resources  
City, State, ZIP code : MINNEOLA, KS 67865- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \					
1	---	NW	---	NE	---
M					
i	W	---		---	E
l					
e					
\ /		SW	---	SE	---

4 DEPTH OF COMPLETED WELL 125 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 81 ft. below land surface measured on mo/day/yr 03/17/05  
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 125 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
Blank casing diameter 5 in. to 105 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS:	From 105 ft. to 125 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 30 ft. to 125 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
Grout Intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: SEPTIC TANK  
Direction from well? NORTH How many feet? 75

LITHOLOGIC LOG			PLUGGING INTERVALS	
FROM	TO		FROM	TO
0	72	TAN CLAY		
72	123	SANDSTONE		
123	125	GRAY CLAY		

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/17/05 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 04/01/05  
under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse