

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 013 CLARK SW 1/4 NW 1/4 NE 1/4 24 T 30 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?  
 6 E. 1 S. OF MINNEOLA, KANS.

2 WATER WELL OWNER: AUSTIN FARMS 071 Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box # : Application Number:  
 City, State, ZIP code : BUCKLIN, KS -

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 100 ELEVATION:  
 Depth(s) Groundwater Encountered 1. 60 ft. 2. ft. 3. ft.  
 WELL'S STATIC WATER LEVEL 60 ft. below land surface measured on mo/day/yr 6 / 4 / 91  
 Pump testdata: Well water was ft. after hours pumping gpm  
 Estimated Yield gpm: Well water was ft. after hours pumping gpm  
 Bore Hole Diameter 8.75 in. to 100 ft., and in. to ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 80 ft., Dia in. to ft., Dia in. to ft.  
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 80 ft. to 100 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 80 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From ft. to 20 ft., From ft. to ft., From ft. to ft.  
 What is the nearest source of possible contamination: CATTLE PASTURE  
 Direction from well? ALL How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	2	SILT & SAND			
2	54	TAN CLAY			
54	60	05 SAND AND 17 GRAVEL			
60	75	05 SAND AND 17 GRAVEL			
75	100	SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 6 / 4 / 91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 06/10/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse