

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: NEADE	Fraction SW 1/4 NW SW 1/4 1/4	Section Number 14	Township Number T 30 S	Range Number R 26 W	
Distance and direction from nearest town or city street address of well if located within city? FROM FOWLER - 2 NORTH, 2 EAST, 2 NORTH, 1 EAST & 1/2 SOUTH					
2 WATER WELL OWNER: RR#, St. Address, Box #: 29001 - C ROAD City, State, ZIP code : FOWLER, KS 67844-		Board of Agriculture, Division of Water Resources Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 185 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.			
<div style="border: 1px dashed black; padding: 5px; text-align: center;"> </div>		WELL'S STATIC WATER LEVEL 80 ft. below land surface measured on mo/day/yr 08/26/98 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm			
		Estimated Yield 12 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm			
		Bore Hole Diameter 9 in. to 185 ft., and in. to 0 ft.			
		WELL WATER TO BE USED AS: DOMESTIC			
Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes					
5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED Blank casing diameter 5 in. to 185 ft., Dia in. to 0 ft., Dia in. to 0 ft. Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC SCREEN OR PERFORATION OPENINGS ARE: SAW CUT					
SCREEN PERFORATED INTERVALS: From 120 ft. to 140 ft., From 0 ft. to 0 ft. From 160 ft. to 180 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 25 ft. to 185 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.					
6 GROUT MATERIAL BENTONITE Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft. What is the nearest source of possible contamination: NONE - NEW SITE Direction from well? How many feet? 0					
FROM 0 20 60 80 100 120 140 160 180	TO 20 60 80 100 120 140 160 180 200	LITHOLOGIC LOG TOPSOIL CLAY FINE SAND FINE SAND FINE - MED SAND FINE - MED SAND CLAY CLAY MEDIUM SAND IN LAYERS CLAY SANDSTONE IN LAYERS CLAY SANDSTONE BLUE CLAY ROCK LAYERS SANDSTONE TAN IN COLOR SANDSTONE TAN IN COLOR BLUE CLAY	FROM	TO	PLUGGING INTERVALS
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/02/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/08/98 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Joe's Well Service</i>					