

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 WEADE NW 1/4 NE 1/4 NE 1/4 12 T 30 S R 27 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6 MILES NORTH AND 1 1/4 MILES WEST OF FOWLER

2 WATER WELL OWNER: ORLIN V. HEYEN
 RR#, St. Address, Box #: RT. 3, BOX 33 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: STAFFORD, KS 67578- Application Number: 15,592

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 245 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 101 ft. below land surface measured on mo/day/yr 07/06/94
 Pump testdata: Well water was 210 ft. after 4 hours pumping 1296 gpm
 Estimated Yield 1150 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 245 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 16 in. to 245 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 16 lbs/ft. Wall thickness or gauge No. .500
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 175 ft. to 235 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 245 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? EAST How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	15	04 SANDY CLAY 07 FINE SAND			
15	43	01 CLAY			
43	72	07 FINE SAND 09 COARSE SAND 01 CLAY			
72	99	01 CLAY 07 FINE SAND			
99	110	07 FINE SAND 09 COARSE SAND 01 CLAY			
110	148	01 CLAY 07 FINE SAND			
148	170	01 CLAY			
170	238	07 FINE SAND 09 COARSE SAND			
238	250	01 CLAY 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/30/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/07/94 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruno Reichmuth*