

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
 COUNTY: 060 MEADE : SW 1/4 NW 1/4 SE 1/4 : 23 : T 30 S : R 27 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 8 1/2 MILES NORTH & 5 MILES EAST OF MEADE

2 WATER WELL OWNER: SCHUBERT & BUTCHER ESTATE
 RR#, St. Address, Box #: BOX 913 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : HUTCHINSON, KS 67504- Application Number: 16836

3 LOCATE WELL'S LOCATION WITH : 4 DEPTH OF COMPLETED WELL 260 ELEVATION: 0
 AN "X" IN SECTION BOX: : Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 / \ : WELL'S STATIC WATER LEVEL 75 ft. below land surface measured on mo/day/yr 05/11/94
 : Pump testdata: Well water was 146 ft. after 1 hours pumping 1761 gpm!
 1 --- NW --- NE ---
 : Estimated Yield 1700 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm!
 W : Bore Hole Diameter 24 in. to 260 ft., and in. to 0 ft.
 : WELL WATER TO BE USED AS: 02 IRRIGATION
 e X
 : Was a chemical/bacteriological sample submitted to department? No ;
 \ / : If yes, mo/day/yr sample was submitted Water well disinfected? Yes!

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 16 in. to 260 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 16 lbs/ft. Wall thickness or gauge No. .50
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 160 ft. to 260 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 260 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTH How many feet? 275!

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	9	01 CLAY 04 SANDY CLAY			
9	41	04 SANDY CLAY 05 SAND			
41	53	04 SANDY CLAY 05 SAND			
53	72	01 CLAY			
72	87	01 CLAY			
87	124	01 CLAY 19 SHALE			
124	152	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
152	169	07 FINE SAND 01 CLAY			
169	182	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/10/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 060 MEADE : SW 1/4 NW 1/4 SE 1/4 : 23 : T 30 S : R 27 W

2 WATER WELL OWNER: SCHUBERT & BUTCHER ESTATE

RR#, St. Address, Box #: BOX 913

Board of Agriculture, Division of Water Resources

City, State, ZIP code : HUTCHINSON, KS 67504-

Application Number: 16836

FROM	TO	LITHOLOGIC LOG
182	235	08 MEDIUM SAND 09 COARSE SAND 15 CRS GRAVEL
235	256	05 SAND 11 GRAVEL 01 CLAY
256	263	04 SANDY CLAY 05 SAND
263	295	01 CLAY 20 LIMESTONE
295	302	04 SANDY CLAY 28 ROCK 01 CLAY
302	330	19 SHALE 01 CLAY
330	344	07 FINE SAND 06 VERY FN SAND 19 SHALE
344	347	19 SHALE 06 VERY FN SAND
347	366	19 SHALE 01 CLAY 07 FINE SAND
366	396	19 SHALE
396	402	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/10/94 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/16/94
under the business name of HENKLE DRILLING & SUPPLY by (signature)