


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Meade</b>	Fraction <b>NE 1/4 SE 1/4 NE 1/4</b>	Section number <b>8</b>	Township number <b>T 30 S</b>	Range number <b>R 27 E</b>
2. Distance and direction from nearest town or city: <b>5 mi. west and 4 1/4 north of Fowler</b> Street address of well location if in city:			3. Owner of well: <b>Dale Zortman et al</b> R.R. or street: <b>Fowler, Kansas</b> City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. <b>28</b> in. Completion date <b>1-28-76</b> Well depth <b>390</b> ft.	
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Surface		0	3	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Brown caleche clay		3	16	9. Casing: Material <b>Metal</b> Height: <del>114</del> or better	
Fine sand		16	30	Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12 above in.</b>	
Clay		30	34	RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>36.87 lbs./ft.</b>	
Med. sand and gravel		34	45	Dia. <b>16</b> in. to <b>390</b> ft. depth Wall Thickness: inches or	
Fine sand with 25% clay mixed		45	75	Dia. in. to ft. depth gage No. <b>219</b>	
Med. sand and fine gravel		75	90	10. Screen: Manufacturer's name <b>W. A. Brown</b>	
Fine brown sand		90	172	Type <b>10% Free-flow</b> Dia. <b>16</b>	
Brown clay		172	175	Slot/gauze <b>1/8</b> Length <b>220</b>	
<del>Med. sand &amp; fine gravel</del>		175	195	Set between <b>170</b> ft. and <b>390</b> ft.	
Sandy yellow clay		193	200	Gravel pack? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <b>3/8 down</b> CMA	
Medium sand and fine gravel with small layer		200	300	11. Static water level: <b>97</b> ft. below land surface Date <b>1-31-76</b>	
Sandy yellow and blue clay		300	339	12. Pumping level below land surfaces: <b>120</b> ft. after <b>3</b> hrs. pumping <b>1350</b> g.p.m.	
Medium sand and gravel		339	350	ft. after hrs. pumping g.p.m.	
Sandy caleche clay		350	368	Estimated maximum yield <b>2000</b> g.p.m.	
Med. sand and gravel		368	388	13. Water sample submitted: mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date	
Brown and yellow clay		388	428	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade	
Blue shale		428	435	15. Well grouted? <b>No</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete	
				Depth: From ft. to ft.	
				16. Nearest source of possible contamination: <b>NA</b> ft. Direction Type	
				Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
				17. Pump: <input checked="" type="checkbox"/> Not installed	
				Manufacturer's name	
				Model number HP Volts	
				Length of drop pipe ft. capacity g.p.m.	
				Type:	
				<input type="checkbox"/> Submersible <input type="checkbox"/> Turbine	
				<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating	
				<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Ace-Hi Int. 190</b> Business name License No. Address <b>Dodge City, Kansas</b> Signed <b>Carl G. Juhl</b> Date <b>2-7-76</b> Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5