

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE SE 1/4 SE 1/4 SE 1/4 15 T 30 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 9.5 MILES NORTH AND 1.0 MILE WEST OF MEADE.

2 WATER WELL OWNER: BRAD BOYD
 RR#, St. Address, Box #: HCR 2, BOX 17 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: FOWLER, KS 67844- Application Number: 40,194

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 356 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 156 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 156 ft. below land surface measured on mo/day/yr 05/12/92
 Pump testdata: Well water was 227 ft. after 4 hours pumping 1757 gpm
 Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 0 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 356 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 236 ft. to 356 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 356 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	26	04 SANDY CLAY 20 LIMESTONE 31 CALICHE			
26	35	05 SAND 11 GRAVEL			
35	53	04 SANDY CLAY 05 SAND			
53	90	05 SAND 13 FINE GRAVEL			
90	111	04 SANDY CLAY			
111	120	05 SAND 13 FINE GRAVEL			
120	126	01 CLAY			
126	139	07 FINE SAND 08 MEDIUM SAND			
139	145	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/11/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas A. Henkle

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	SE 1/4 SE 1/4 SE 1/4	15	T 30 S	R 28 W

2 WATER WELL OWNER: BRAD BOYD
 RR#, St. Address, Box #: HCR 2, BOX 17 Board of Agriculture, Division of Water Resources

City, State, ZIP code : FOWLER, KS 67844- Application Number: 40,194

FROM	TO	LITHOLOGIC LOG
145	150	05 SAND
150	159	04 SANDY CLAY
159	181	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
181	184	04 SANDY CLAY
184	203	01 CLAY
203	205	05 SAND
205	235	01 CLAY
235	246	05 SAND
246	250	04 SANDY CLAY
250	273	05 SAND 13 FINE GRAVEL
273	274	04 SANDY CLAY
274	291	05 SAND 13 FINE GRAVEL
291	335	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
335	339	04 SANDY CLAY
339	343	05 SAND
343	349	04 SANDY CLAY
349	353	05 SAND
353	401	04 SANDY CLAY 20 LIMESTONE 05 SAND

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/11/92 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Douglas R. Henkle