

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 060 MEADE SE 1/4 NE 1/4 SW 1/4 23 T 30 S R 29 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM MISSLER; 6 1/2 MILES NORTH & 1 1/4 MILES WEST

2 WATER WELL OWNER: JUDY GAMBLE Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: 2107 GRANGE DR Application Number: 6243
 City, State, ZIP code: URBANA, IL 61801-6608

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \																				
1		NW		NE																
M	W																			E
i																				
l																				
e			SW	X	SE															
\ /																				

4 DEPTH OF COMPLETED WELL 545 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 222 ft. below land surface measured on mo/day/yr 02/21/06
 Pump test data: Well water was 234 ft. after 4 hours pumping 1575 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 545 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 545 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 240 ft. to 380 ft., From 480 ft. to 540 ft.
 From 414 ft. to 464 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 545 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? EAST How many feet? 285

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	20	01 CLAY 31 CALICHE			
20	38	05 SAND 01 CLAY			
38	60	07 FINE SAND			
60	74	07 FINE SAND 08 MEDIUM SAND			
74	98	01 CLAY 20 LIMESTONE			
98	141	05 SAND 13 FINE GRAVEL			
141	152	01 CLAY			
152	174	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
174	193	01 CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/16/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/19/06 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 060 MEADE SE 1/4 NE 1/4 SW 1/4 23 T 30 S R 29 W

2 WATER WELL OWNER: JUDY GAMBLE
RR#, St. Address, Box # : 2107 GRANGE DR Board of Agriculture, Division of Water Resources
City, State, ZIP code : URBANA, IL 61801-6608 Application Number: 6243

FROM	TO	LITHOLOGIC LOG
193	280	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
275	285	06 VERY FN SAND 07 FINE SAND 01 CLAY
310	340	05 SAND 11 GRAVEL 01 CLAY
340	379	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
379	411	01 CLAY
411	434	01 CLAY 07 FINE SAND
434	444	07 FINE SAND 01 CLAY
444	464	07 FINE SAND 04 SANDY CLAY 20 LIMESTONE
464	475	01 CLAY
485	500	07 FINE SAND 01 CLAY
500	520	07 FINE SAND
520	540	07 FINE SAND 08 MEDIUM SAND
540	550	01 CLAY
550	560	19 SHALE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/16/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/19/06 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

