

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Meade	Fraction SE 1/4 NW 1/4 NW 1/4	Section number 33	Township number T 30 S R 29 E/W	Range number
2. Distance and direction from nearest town or city: 3 1/2 West, 12 3/4 South, 50 Ft. East of			3. Owner of well: Daniel Dirks			
Street address of well location if in city: Montezuma, Ks.			R.R. or street: Montezuma, Ks.			
City, state, zip code:						
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 26 in. Completion date 11-18-75		
N		Well depth 415 ft.		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug		
NW NE		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry		<input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock		
SW SE		9. Casing: Material <u>steel</u> Weight: Above or below		<input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
E		Threading: <input type="checkbox"/> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in.		RMP 16 PVC 116 Weight 36.8 lbs./ft.		
W		Dia. 16 in. to 116 ft. depth; Wall Thickness: inches or		Dia. <u> </u> in. to <u> </u> ft. depth; gage No. <u> </u>		
S		1 Mile		10. Screen: Manufacturer's name <u> </u>		
1 Mile				No Screen		
				Type <u> </u> Dia. <u> </u>		
				Slot/gauze <u> </u> Length <u> </u>		
				SP between 220 415 ft. and <u> </u> ft.		
				<u> </u> ft. and <u> </u> ft.		
				Gravel pack? <input checked="" type="checkbox"/> yes <input type="checkbox"/> no 1/2" Down		
				11. Static water level: 134 ft. below land surface Date 11-18-75		
				12. Pumping level below land surfaces: 154 ft. after 2 hrs. pumping 825 g.p.m.		
				162 ft. after 4 hrs. pumping 1209 g.p.m.		
				Estimated maximum yield 1200 g.p.m.		
				13. Water sample submitted: <u> </u> mo./day/yr.		
				Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Date <u> </u>		
				14. Well head completion: 12		
				<input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> yes <u> </u> inches above grade		
				15. Well grouted? <u> </u>		
				With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete		
				Depth: From <u> </u> ft. to 10 ft.		
				16. Nearest source of possible contamination: N/A		
				ft. <u> </u> Direction <u> </u> Type <u> </u>		
				Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
				17. Pump: <input checked="" type="checkbox"/> Not installed		
				Manufacturer's name <u> </u>		
				Model number <u> </u> HP <u> </u> Volts <u> </u>		
				Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m.		
				Type:		
				<input type="checkbox"/> Submersible <input type="checkbox"/> Turbine		
				<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating		
				<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography:				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
<input checked="" type="checkbox"/> Hill				Minter-Wilson Drilling 208		
<input type="checkbox"/> Slope				Business name J.O.B. A. Harden City License No. <u> </u>		
<input type="checkbox"/> Upland				Address <u> </u>		
<input type="checkbox"/> Valley				Signed <u> </u> Date 11-30-75		
				Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

The
Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Daniel Dirks
Meade County
9-20-75

Location: NW 33-30-29 $\frac{3}{4}$ miles West of Montezuma, 12 $\frac{3}{4}$ mi
South, 50 ft. East

Test # 1

0	5	Top Soil
5	20	Brown Clay
20	43	Brown Sandy Clay
43	52	Fine Sand
52	103	Fine to Med. Sand & Gravel
103	110	Brown Sandy Clay
110	168	Fine to Med. Sand & Gravel (Loose)
168	197	Brown Sandy Clay
197	415	Fine to Med. Sand & Gravel (Loose)
415	425	Gray & Brown Clay (Hard)

TD 415'

END OF ROLL

ROLL