

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
 COUNTY: 060 WEADE : NW 1/4 SW 1/4 NE 1/4 : 31 : T 30 S : R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 8 3/4 NORTH, & 2 1/2 MILES WEST OF PLAINS

2 WATER WELL OWNER: HULBURT, PAULINE
 RR#, St. Address, Box #: 115 DELLWOOD Board of Agriculture, Division of Water Resources
 City, State, ZIP code : ATHENS, KS 67864- Application Number: 33,565

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: : 4 DEPTH OF COMPLETED WELL 438 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 207 ft. below land surface measured on mo/day/yr 04/06/95	
Pump test data: Well water was 290 ft. after 4 hours pumping 1500 gpm	
Estimated Yield 1500 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm	
Bore Hole Diameter 24 in. to 438 ft., and in. to 0 ft.	
WELL WATER TO BE USED AS: 02 IRRIGATION	
Was a chemical/bacteriological sample submitted to department? No ;	
If yes, mo/day/yr sample was submitted Water well disinfected? Yes	

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 438 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .25
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 280 ft. to 360 ft., From 425 ft. to 435 ft.
 From 380 ft. to 410 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 438 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 0 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	6	01 CLAY			
6	50	04 SANDY CLAY 31 CALICHE 04 SANDY CLAY			
50	55	04 SANDY CLAY 07 FINE SAND			
55	84	04 SANDY CLAY 20 LIMESTONE			
84	93	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
93	97	04 SANDY CLAY			
97	137	05 SAND 13 FINE GRAVEL 01 CLAY			
137	143	01 CLAY 04 SANDY CLAY			
143	157	07 FINE SAND 09 COARSE SAND 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/04/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/20/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 060 MEADE	NW 1/4 SW 1/4 NE 1/4	31	T 30 S	R 30 W

2 WATER WELL OWNER:	HULBURT, PAULINE	Board of Agriculture, Division of Water Resources Application Number: 33,565
RR#, St. Address, Box # :	115 DELLWOOD	
City, State, ZIP code :	ATHENS, KS 67864-	

FROM	TO	LITHOLOGIC LOG
157	164	01 CLAY 04 SANDY CLAY
164	174	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
174	179	04 SANDY CLAY
179	187	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
187	196	04 SANDY CLAY 07 FINE SAND 09 COARSE SAND
196	204	04 SANDY CLAY
204	231	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
231	251	01 CLAY
251	360	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
360	380	01 CLAY
380	412	05 SAND 01 CLAY
412	422	29 ROCK & SAND 21 SHALE & LMST 04 SANDY CLAY
422	425	20 LIMESTONE
425	435	23 SANDSTONE 31 CALICHE
435	442	31 CALICHE 01 CLAY
442	502	01 CLAY 04 SANDY CLAY 21 SHALE & LMST
502	526	01 CLAY 31 CALICHE
526	529	20 LIMESTONE 31 CALICHE 19 SHALE
529	542	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/04/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/20/95 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bruce J. Reichmuth*