

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NW 1/4 NW 1/4 NE 1/4 15 T 30 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6 MILES EAST, 2 SOUTH & 1 1/2 EAST OF SUBLETTE

2 WATER WELL OWNER: STAPLETON, LEROY
 RR#, St. Address, Box #: 4308 RIDERS MARK Board of Agriculture, Division of Water Resources
 City, State, ZIP code: EDMOND, KS 67877- Application Number: 462

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 500 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 279 ft. below land surface measured on mo/day/yr 10/25/96
 Pump testdata: Well water was 350 ft. after 4 hours pumping 1200 gpm
 Estimated Yield 1200 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 500 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 500 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., Weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 317 ft. to 497 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 500 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	30	04 SANDY CLAY 31 CALICHE			
30	42	04 SANDY CLAY 07 FINE SAND 31 CALICHE			
42	50	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
50	59	04 SANDY CLAY 07 FINE SAND 31 CALICHE			
59	70	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
70	111	05 SAND 13 FINE GRAVEL 01 CLAY			
111	128	05 SAND 11 GRAVEL 04 SANDY CLAY			
128	180	05 SAND 01 CLAY			
180	195	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 10/23/96 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/31/96
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 041 HASKELL NW 1/4 NW 1/4 NE 1/4 15 T 30 S R 31 W

2 WATER WELL OWNER: STAPLETON, LEROY

RR#, St. Address, Box # : 4308 RIDERS MARK

City, State, ZIP code : EDMOND, KS 67877-

Board of Agriculture, Division of Water Resources
Application Number: 462

FROM	TO	LITHOLOGIC LOG
195	213	04 SANDY CLAY 07 FINE SAND
213	241	05 SAND 13 FINE GRAVEL
241	262	04 SANDY CLAY 05 SAND
262	285	07 FINE SAND 08 MEDIUM SAND 01 CLAY
285	305	01 CLAY
305	335	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
335	355	07 FINE SAND 08 MEDIUM SAND 01 CLAY
355	368	05 SAND 13 FINE GRAVEL
368	383	01 CLAY
383	396	17 SAND & GRAVL 20 LIMESTONE 01 CLAY
396	405	04 SANDY CLAY
405	415	05 SAND 01 CLAY
415	474	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
474	497	05 SAND 28 ROCK 01 CLAY
497	520	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) 10/23/96 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/31/96
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmuth*