


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Haskell	Fraction SW 1/4 SW 1/4 NW 1/4	Section number 15	Township number 30	Range number 31	
2. Distance and direction from nearest town or city: Approximately 7 1/2 miles E and 2 1/2 South of Sublette, Ks.				3. Owner of well: LeRoy Stapleton City, state, zip code: Sublette, Kansas 67877			
4. Locate with "X" in section below: 				Sketch map:			
5. Type and color of material				From	To		
				<i>Attached</i>			
6. Bore hole dia. 11 in. Completion date 7/09/78 Well depth 393 ft.							
7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary							
8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other							
9. Casing: Material Plastic Height: Above or below Glued Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight 4.0 lbs./ft. Dia. 6 5/8 in. to 393 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 316							
10. Screen: Manufacturer's name Jet Stream Type PVC Dia. 6 5/8 " Slot/gauze 040 Length 60 ' Set between 370 ft. and 390 ft. 300'-320' ft. and 330'-350' ft. Gravel pack? Yes Size range of material 8-12 Fountain							
11. Static water level: ☐ mo./day/yr. 215 ft. below land surface Date 7/12/78							
12. Pumping level below land surface Not Pumped ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield 50 g.p.m.							
13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date _____							
14. Well head completion: ☒ Pitless adapter 12 inches above grade							
15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.							
16. Nearest source of possible contamination: ft. 400 Direction East Type Cattle Well disinfected upon completion? ☒ Yes ☐ No							
17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other							
(Use a second sheet if needed)							
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Henkle Drilling & Sply 145 Business name License No. _____ Address Box 639, Garden City, KS Signed Donna Reichmuth Date 7/20/78 Authorized representative			
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

DRILLERS TEST LOG

CUSTOMERS NAME LeRoy Stapleton
 STREET ADDRESS _____
 CITY & STATE Sublette, Kansas
 COUNTY Haskell QUARTER NW SECTION 15
 LOCATION 400 ft East and 200 ft North of the SW corner of the 4.

DATE 7/10/78
 TEST # 1 E. LOG Yes
 DRILLER Martinez
 TOWNSHIP 30 RANGE 31

ne SW corner of the 4.

DOMESTIC WELL LOCATION

Static Water Level _____

Proposed Well Depth _____

%	FOOTAGE		DESCRIPTION OF STRATA	
	From	Pay To		
	(0)	2	Top Soil	
	2	20	Brown clay	
	20	60	Brown clay with a few limerock sts.	
	60	75	Brown clay with a few sand sts.	
	75	80	Sand fine to med coarse	
	80	85	Brown clay, limerock with a few hard ledges.	
	85	107	Sand fine to med coarse with small to med gravel.	
	107	114	Brown clay	
	114	120	Sand fine to med coarse	
	120	130	Brown clay with a few limerock sts.	
	130	156	Sand fine to med coarse with small to med gravel.	
	156	167	Brown clay	
	167	186	Sand fine to med coarse with small to med gravel.	
	186	195	Brown clay	
	195	218	Sand fine to med coarse and small gravel. Loose - used water.	
	218	230	Brown clay.	
50	230	23	253	Sand fine to med coarse Loose - used water
	253		261	Brown and blue clay
55	261	20	281	Sand fine to med coarse with a few small gravel.
				Loose - used water.
	281		298	Brown and blue clay
55	298	19	317	Sand fine to med coarse with a few small gravel.
				Loose - used water.
	317		325	Brown and blue clay.
60	325	26	351	Sand fine to med coarse and small gravel. Loose - used water.
	351		369	Brown and blue clay.
50	369	22	391	Sand fine to med coarse Loose - used water.
	391		460	Brown clay with a few limerock sts.
	460		470	Yellow clay
	470		480	Weather shale
		110		Casing Schedule:
				0'-300' Plain
				300'-320' Perf.
				320'-330' Plain
				330'-350' Perf.
				350'-370' Plain
				370'-390' Perf.
				390'-393' Plain

Domestic Total Depth 393'

Plastic Casing

2 Gravel Pack

GARDEN CITY, KS

Phone 276-3278

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL

HENKLE DRILLING & SUPPLY CO., INC.

IRRIGATION HEADQUARTERS

Y CO., INC.

ARTERS

WELLS * * * * STOCK WELLS

SUBLETTE, KS

Phone 675-4311