

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

County HASKELL		Fraction NE 1/4 SW 1/4 NW 1/4		Section number 23		Township number T 30 S R 31		Range number NW	
2. Distance and direction from nearest town or city: of Sublette, $\frac{1}{4}$ South, $8\frac{1}{2}$ East, $\frac{1}{2}$ North. Street address of well location if in city:						3. Owner of well: Gary Rexford R.R. or street: City, state, zip code: Meade, Kansas 67864			
4. Locate with "X" in section below: 						Sketch map:			
5. Type and color of material						6. Bore hole dia. <u>26</u> in. Completion date <u>10-15-75</u> Well depth <u>445</u> ft.			
						7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
						8. Use: Domestic ☐ Public supply ☐ Industry ☐ ☒ Irrigation Air conditioning Stock Lawn Oil field water Other			
						9. Casing: Material <u>Steel</u> Height: Above or below Threaded Welded ☒ Surface <u>12</u> in. RMP PVC Weight <u>36.87</u> lbs./ft. Dia. <u>16</u> in. to <u>446</u> ft. depth Wall Thickness: inches or Dia. in. to ft. depth gage No.			
						10. Screen: Manufacturer's name <u>Johnson Division</u> Type <u>Galvanized</u> Dia. <u>16"</u> Slot/gauze Length <u>10'</u> Set between <u>280-290</u> ft. and <u>425-435</u> ft. Perf: <u>220-280</u> ft. and <u>400-425-435-445</u> ft. Gravel pack? <u>yes</u> Size range of material <u>2# Down</u>			
						11. Static water level: mo./day/yr. <u>204</u> ft. below land surface Date <u>9-11-75</u>			
						12. Pumping level below land surfaces: <u>221</u> ft. after <u>2</u> hrs. pumping <u>791</u> g.p.m. <u>233</u> ft. after <u>4</u> hrs. pumping <u>1280</u> g.p.m. Estimated maximum yield <u>1250</u> g.p.m.			
						13. Water sample submitted: mo./day/yr. Yes ☒ No ☐ Date			
						14. Well head completion: Pitless adapter <u>12</u> Inches above grade			
						(Use a second sheet if needed)			
16. Nearest source of possible contamination: ft. Direction Type <u>N/A</u> Well disinfected upon completion? Yes ☒ No ☐									
17. Pump: Not installed Manufacturer's name <u>Goulds - US Pumps</u> Model number <u>K-2111</u> HP <u>180</u> Volts Length of drop pipe <u>300</u> ft. capacity <u>1250</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet Reciprocating ☐ Centrifugal Other									
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Minter-Wilson Drilling</u> <u>208</u> Business name License No. Address <u>Box A Garden City, KS</u> Signed <u>[Signature]</u> Date <u>10/15/75</u> Authorized representative									
18. Elevation:									
19. Remarks:									
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley									

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

The
Professional

MINTER-WILSON DRILLING CO.
INCORPORATED

Drilling
and
Coring
Equipment
and
Supplies
Available
at
All
Times

Phone 275-4111 • P.O. Box 191 • GARDEN CITY, KANSAS 66503

Alvis Rexford (Jury)
Haskell County
8-26-75

Location: 1/4 mile west of No. 1 NW 22-30-31

Test # 2

0	0	Top Soil
0	11	Brown Sandy Clay
41	7	Fine Sand
49	66	Brown Sandy Clay
66	91	Fine to Med. Sand & Gravel (Loose)
71	106	Brown & White Sandy Clay
106	168	Fine to Med. Sand & Gravel (Loose)
168	200	Fine to Med. Sand & Gravel (Tight)
200	260	Fine to Med. Sand & Gravel (Loose)
260	270	Fine to Med. Sand & Gravel, Streaks of Clay (15%)
270	290	Fine to Med. Sand & Gravel (Loose)
290	322	Blue Clay, Small Streaks Fine to Med. Sand & Gravel
322	350	Blue Clay
350	400	Blue Clay, Streaks of Brown Clay
400	412	Fine to Med. Sand (Streaks of Clay 15% Tight)
412	445	Fine to Med. Sand & Gravel, Streaks of Clay (10%)
445	453	Brown & Gray Clay (Hard)
453	455	Shale

TD - 445'
20' Screen