

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 041 HASKELL SW 1/4 SW 1/4 NW 1/4 15 T 30 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?

FROM FAIRGROUNDS CORNER OF SUBLETTE, 2W S & 1W E, 1/2W S

2 WATER WELL OWNER: DIADEN FARMS INC.

RR#, St. Address, Box #: 1420 CROWNHILL

Board of Agriculture, Division of Water Resources

City, State, ZIP code: ARLINGTON, TX 76012-

Application Number: 30454

7431

3 LOCATE WELL'S LOCATION WITH

AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 660 ELEVATION: 0

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \

WELL'S STATIC WATER LEVEL 280 ft. below land surface measured on mo/day/yr 05/30/96

Pump test data: Well water was 489 ft. after 2 hours pumping 760 gpm

1 NW NE

Estimated Yield 760 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

W X

Bore Hole Diameter 24 in. to 660 ft., and in. to 0 ft.

e SW SE

WELL WATER TO BE USED AS: 02 IRRIGATION

\ /

Was a chemical/bacteriological sample submitted to department? No;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 660 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:

From 340 ft. to 500 ft., From 0 ft. to 0 ft.

From 527 ft. to 657 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS:

From 20 ft. to 660 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03-BENTONITE

Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well?

How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	35	04 SANDY CLAY 31 CALICHE			
35	43	01 CLAY 31 CALICHE			
43	54	04 SANDY CLAY 01 CLAY			
54	77	07 FINE SAND 09 COARSE SAND 11 GRAVEL			
77	117	01 CLAY 31 CALICHE 05 SAND			
117	165	07 FINE SAND 09 COARSE SAND 01 CLAY			
165	170	01 CLAY 20 LIMESTONE			
170	225	07 FINE SAND 09 COARSE SAND 11 GRAVEL			
225	300	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

completed on (mo/day/year) 05/23/96 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/24/96

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SW 1/4 NW 1/4	15	T 30 S	R 32 W

2 WATER WELL OWNER:	DIADEN FARMS INC.	Board of Agriculture, Division of Water Resources Application Number: 30454
RR#, St. Address, Box # :	1420 CROWNHILL	
City, State, ZIP code :	ARLINGTON, TX 76012-	

FROM	TO	LITHOLOGIC LOG
300	337	04 SANDY CLAY
337	342	07 FINE SAND 09 COARSE SAND 11 GRAVEL
342	355	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
355	383	04 SANDY CLAY
383	428	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
428	440	04 SANDY CLAY
440	500	04 SANDY CLAY 20 LIMESTONE
500	505	01 CLAY 24 SAND & SHALE
505	517	24 SAND & SHALE 20 LIMESTONE
517	570	23 SANDSTONE 24 SAND & SHALE
570	575	21 SHALE & LMST
575	651	23 SANDSTONE 21 SHALE & LMST
651	657	24 SAND & SHALE
651	660	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was	Constructed under my jurisdiction and was
completed on (mo/day/year) 05/23/96 and this record is true to	the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145	This water well Record was completed on (mo/day/yr) 06/24/96
under the business name of HENKLE DRILLING & SUPPLY	by (signature) <i>Bruce J. Reichardt</i>