

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NW 1/4 NW 1/4 NW 1/4 19 T 30 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3.25 MILES SOUTH AND 1.25 MILES WEST OF SUBLETTE.

2 WATER WELL OWNER: STOPPEL, TOM
 RR#, St. Address, Box #: P.O. BOX 592 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SUBLETTE, KS 67877- Application Number: 7,820 & 2,649

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 635 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 316 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 316 ft. below land surface measured on mo/day/yr 09/03/92
 Pump test data: Well water was 390 ft. after 4 hours pumping 1077 gpm
 Estimated Yield 1000 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 635 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 635 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 332 ft. to 402 ft., From 570 ft. to 630 ft.
 From 412 ft. to 462 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 635 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? EAST How many feet? 250

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	70	04 SANDY CLAY 31 CALICHE 07 FINE SAND			
70	85	08 MEDIUM SAND 13 FINE GRAVEL 14 MED GRAVEL			
85	136	04 SANDY CLAY 31 CALICHE			
136	223	08 MEDIUM SAND 13 FINE GRAVEL 14 MED GRAVEL			
223	239	01 CLAY			
239	266	05 SAND 14 MED GRAVEL 01 CLAY			
266	280	01 CLAY 05 SAND			
280	300	01 CLAY			
300	313	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/01/92 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/20/92
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 041 HASKELL NW 1/4 NW 1/4 NW 1/4 19 T 30 S R 32 W

2 WATER WELL OWNER: STOPPEL, TOM
RR#, St. Address, Box #: P.O. BOX 592 Board of Agriculture, Division of Water Resources
City, State, ZIP code: SUBLETTE, KS 67877- Application Number: 7,820 & 2,649

FROM	TO	LITHOLOGIC LOG
313	317	01 CLAY
317	352	05 SAND 13 FINE GRAVEL
352	360	01 CLAY
360	382	05 SAND 13 FINE GRAVEL
382	402	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
402	412	04 SANDY CLAY 20 LIMESTONE 05 SAND
412	418	05 SAND 13 FINE GRAVEL
418	462	20 LIMESTONE 04 SANDY CLAY 07 FINE SAND
462	477	19 SHALE 20 LIMESTONE
477	567	19 SHALE
567	632	23 SANDSTONE 19 SHALE
632	642	19 SHALE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/01/92 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/20/92
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmann*