

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NE 1/4 NE 1/4 SW 1/4 30 T 30 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 4 1/2 MILES SOUTH AND 1/2 EAST OF SUBLETTE.

2 WATER WELL OWNER: JERRY EVANS
 RR#, St. Address, Box #: P.O. BOX 188 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SUBLETTE, KS 67877- Application Number: 23710

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 569 ELEVATION:
 Depth(s) Groundwater Encountered 1. 285 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 285 ft. below land surface measured on mo/day/yr 05/28/91
 Pump test data: Well water was 313 ft. after 4 hours pumping 1380 gpm
 Estimated Yield 1350 gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 24 in. to 569 ft., and in. to ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 569 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 34 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 337 ft. to 397 ft., From 487 ft. to 497 ft.
 From 430 ft. to 460 ft., From 525 ft. to 565 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 569 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From ft. to 20 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 2630

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	2	01 CLAY			
2	65	04 SANDY CLAY 05 SAND			
65	84	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
84	123	04 SANDY CLAY 05 SAND			
123	142	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
142	145	04 SANDY CLAY			
145	242	08 MEDIUM SAND 13 FINE GRAVEL 14 MED GRAVEL			
242	279	01 CLAY			
279	301	07 FINE SAND 08 MEDIUM SAND			
301	397	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/21/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/20/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas B. Henkle

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 041 HASKELL NE 1/4 NE 1/4 SW 1/4 30 T 30 S R 32 W

2 WATER WELL OWNER: JERRY EVANS
RR#, St. Address, Box #: P.O. BOX 188

Board of Agriculture, Division of Water Resources

City, State, ZIP code : SUBLETTE, KS 67877-

Application Number: 23710

FROM	TO	LITHOLOGIC LOG
397	428	04 SANDY CLAY 05 SAND
428	463	19 SHALE 23 SANDSTONE
463	487	19 SHALE
487	496	23 SANDSTONE
496	525	19 SHALE
525	566	23 SANDSTONE 19 SHALE
566	622	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/21/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/20/91 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Douglas B. Henkle