

TEST HOLE REPORT

MIDWEST WELL & PUMP

P.O. BOX 692 • GARDEN CITY, KANSAS 67846 • 316/ 275-1920

| | | |
|---|---------------------|--|
| Contract Name <u>Hutchinson National Bank</u> | | <div style="border: 2px solid black; padding: 5px; width: fit-content; margin: 0 auto;"> TEST HOLE No. <u>87-3</u> </div> |
| Job No. _____ | Date <u>8-1-87</u> | |
| City <u>Sublette</u> | State <u>Kansas</u> | Driller <u>Soukup</u> |
| Location of Test Hole <u>275' East of</u> <u>present well</u> | | <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto; display: flex; flex-wrap: wrap;"> <div style="width: 50%; height: 50%;"></div> <div style="width: 50%; height: 50%;"></div> <div style="width: 50%; height: 50%;"></div> <div style="width: 50%; height: 50%;"></div> </div> |
| <u>1/4 SW 1/4 Sec. 33 of T 30</u> <u>R 32, Haskell Co., Kansas</u> | | |
| | | Elevation of Test Hole _____ Static Water Level <u>245'</u> Measured _____ Hours After Completion |

| From | To | Description of Strata | Water Bearing |
|------|-----|--|---------------|
| 0 | 1 | top soil | |
| 1 | 60 | brown clay & gypsum | |
| 60 | 80 | fine & coarse sand, hard streaks | |
| 80 | 115 | brown clay & gypsum | |
| 115 | 140 | fine & coarse sand | |
| 140 | 160 | fine & coarse sand, small gravel, cemented streaks | |
| 160 | 180 | fine & coarse sand, small gravel & clay streaks | |
| 180 | 235 | fine & coarse sand, small gravel & hard streaks | |
| 235 | 240 | gray clay | |
| 240 | 260 | fine & coarse sand, some small gravel | |
| 260 | 276 | brown clay, sticky | |
| 276 | 280 | fine sand | |
| 280 | 310 | fine medium sand, few clay streaks | |
| 310 | 325 | brown & gray clay | |
| 325 | 330 | Medium & coarse sand, few clay streaks | |
| 330 | 342 | Medium & coarse sand, small gravel | |
| 342 | 362 | Medium & coarse sand, small gravel, hard streaks | |
| 362 | 382 | Medium & coarse sand, small gravel | |
| 382 | 389 | Fine & medium sand, few clay streaks | |
| 389 | 404 | Fine sand & clay mixed | |

Remarks:

