

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL SW 1/4 SW 1/4 NW 1/4 34 T 30 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 5.5 MILES SOUTH AND 1.25 MILES EAST OF SUBLETTE.

2 WATER WELL OWNER: HALEY, EUGENE
 RR#, St. Address, Box #: P.O. BOX 904 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LAWRENCE, KS 66044- Application Number: 14,001 & 18,781

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 543 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 264 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 262 ft. below land surface measured on mo/day/yr 12/10/92
 Pump testdata: Well water was 359 ft. after 4 hours pumping 1287 gpm
 Estimated Yield 1200 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 543 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 543 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 40 lbs/ft. Wall thickness or gauge No. .236
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 308 ft. to 388 ft., From 0 ft. to 0 ft.
 From 440 ft. to 540 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 543 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHWEST How many feet? 282

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	01 CLAY			
3	20	01 CLAY			
20	39	01 CLAY 20 LIMESTONE 05 SAND			
39	59	05 SAND 35 CLAY & GRAVL 20 LIMESTONE			
59	65	01 CLAY			
65	95	01 CLAY 05 SAND 23 SANDSTONE			
95	136	05 SAND 11 GRAVEL			
136	140	01 CLAY 05 SAND			
140	145	05 SAND 11 GRAVEL			
145	264	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/10/92 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/16/92
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

12 WATER WELL OWNER: HALEY, EUGENE
1 RR#, St. Address, Box #: P.O. BOX 904
1 City, State, ZIP code : LAWRENCE, KS 66044-
Board of Agriculture, Division of Water Resources
Application Number: 14,001 & 18,781

FROM		TO	LITHOLOGIC LOG
264	280	05	SAND
280	290	01	CLAY
290	299	05	SAND
299	308	01	CLAY
308	358	05 SAND 13 FINE GRAVEL 14 MED GRAVEL	
358	388	04 SANDY CLAY 23 SANDSTONE 20 LIMESTONE	
388	438	01	CLAY
438	470	04 SANDY CLAY 07 FINE SAND	
470	540	23	SANDSTONE
540	560	19	SHALE

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
18 completed on (mo/day/year) 12/10/92 and this record is true to the best of my knowledge and belief. Kansas
19 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/16/92
20 under the business name of HENKLE DRILLING & SUPPLY by (signature) *[Signature]*

by (signature