

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: **041 HASKELL** SW 1/4 SW 1/4 NW 1/4 **05** T **30** S R **32** W

Distance and direction from nearest town or city street address of well if located within city?  
**FROM SUBLETTE; APPX 1/4 MILE SOUTH**

2 WATER WELL OWNER: **RICK REDD**  
 RR#, St. Address, Box # : **PO BOX 296** Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : **SUBLETTE, KS 67877-0296** Application Number: **8,164**

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL **696** ELEVATION: **0**  
 Depth(s) Groundwater Encountered 1. **0** ft. 2. **0** ft. 3. **0** ft.  
 WELL'S STATIC WATER LEVEL **345** ft. below land surface measured on mo/day/yr **05/04/07**  
 Pump test data: Well water was **449** ft. after **4** hours pumping **910** gpm  
 Estimated Yield **0** gpm: Well water was **0** ft. after **0** hours pumping **0** gpm  
 Bore Hole Diameter **24** in. to **696** ft., and in. to **0** ft.  
 WELL WATER TO BE USED AS: **02 IRRIGATION**  
 Was a chemical/bacteriological sample submitted to department? **No** ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? **Yes**

5 TYPE OF BLANK CASING USED: **01 STEEL** CASING JOINTS: **WELDED**  
 Blank casing diameter **16** in. to **696** ft., Dia in. to **0** ft., Dia in. to **0** ft.  
 Casing height above land surface **12** in., weight **42** lbs/ft. Wall thickness or gauge No. **.250**  
 TYPE OF SCREEN OR PERFORATION MATERIAL: **01 STEEL**  
 SCREEN OR PERFORATION OPENINGS ARE: **01 CONT. SLOT**

SCREEN PERFORATED INTERVALS: From **377** ft. to **417** ft., From **0** ft. to **0** ft.  
 From **441** ft. to **691** ft., From **0** ft. to **0** ft.  
 GRAVEL PACK INTERVALS: From **20** ft. to **696** ft., From **0** ft. to **0** ft.  
 From **0** ft. to **0** ft., From **0** ft. to **0** ft.

6 GROUT MATERIAL **03 BENTONITE**  
 Grout Intervals: From **0** ft. to **20** ft., From **0** ft. to **0** ft., From **0** ft. to **0** ft.  
 What is the nearest source of possible contamination: **14 ABAND. WELL**  
 Direction from well? **SOUTHWEST** How many feet? **209**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	68	04 SANDY CLAY 20 LIMESTONE			
68	79	04 SANDY CLAY			
79	90	05 SAND 13 FINE GRAVEL			
90	115	04 SANDY CLAY			
115	120	05 SAND			
120	138	04 SANDY CLAY 05 SAND			
138	159	05 SAND 11 GRAVEL			
159	180	04 SANDY CLAY 05 SAND			
180	228	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **05/02/07** and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. **145** This Water Well Record was completed on (mo/day/yr) **06/28/07**  
 under the business name of **HENKLE DRILLING & SUPPLY** by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SW 1/4 NW 1/4	05	T 30 S	R 32 W

2 WATER WELL OWNER:	RICK REDD	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	PO BOX 296	Application Number: 8,164
City, State, ZIP code :	SUBLETTE, KS 67877-0296	

FROM	TO	LITHOLOGIC LOG
228	236	04 SANDY CLAY
236	246	04 SANDY CLAY
246	279	05 SAND 13 FINE GRAVEL
279	326	01 CLAY 05 SAND
326	330	05 SAND
330	347	04 SANDY CLAY 07 FINE SAND
347	357	05 SAND
357	397	05 SAND 13 FINE GRAVEL
397	417	05 SAND 01 CLAY
417	443	04 SANDY CLAY 05 SAND
443	691	23 SANDSTONE 31 CALICHE
691	700	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/02/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/28/07 under the business name of HENKLE DRILLING & SUPPLY by (signature) 