

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NW 1/4 NW 1/4 NE 1/4	30	T 30 S	R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SUBLETTE, APPX 4 MILES SOUTH

2 WATER WELL OWNER: W.E. LAND & CATTLE

RR#, St. Address, Box # : PO BOX 864

Board of Agriculture, Division of Water Resources

City, State, ZIP code : HASKELL, KS 67877-

Application Number: 23,710

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \			X		
1	---	NW	---	NE	---
M					
i	W	---	---	---	---
1					
e					
		---	---	---	---
		SW		SE	
\ /					
---	---	---	---	---	---

4 DEPTH OF COMPLETED WELL 633 ELEVATION: 0

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 333 ft. below land surface measured on mo/day/yr 04/13/07

Pump test data: Well water was 389 ft. after 4 hours pumping 1315 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 633 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 633 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 370 ft. to 420 ft., From 538 ft. to 628 ft.

From 457 ft. to 467 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 633 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHWEST

How many feet? 304

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	64	04 SANDY CLAY 07 FINE SAND			
64	88	05 SAND 11 GRAVEL			
88	130	04 SANDY CLAY 20 LIMESTONE			
130	329	05 SAND 13 FINE GRAVEL 01 CLAY			
329	336	04 SANDY CLAY			
336	345	05 SAND 13 FINE GRAVEL			
345	351	04 SANDY CLAY			
351	417	05 SAND 13 FINE GRAVEL			
417	457	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/11/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/22/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NW 1/4 NW 1/4 NE 1/4	30	T 30 S	R 32 W

2 WATER WELL OWNER: W.E. LAND & CATTLE

RR#, St. Address, Box # : PO BOX 864

Board of Agriculture, Division of Water Resources

City, State, ZIP code : HASKELL, KS 67877-

Application Number: 23,710

FROM	TO	LITHOLOGIC LOG
457	468	05 SAND
468	537	31 CALICHE 23 SANDSTONE
537	545	23 SANDSTONE
545	551	31 CALICHE
551	573	23 SANDSTONE
573	577	23 SANDSTONE
577	601	23 SANDSTONE
601	628	23 SANDSTONE
628	640	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/11/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/22/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Reichmelt