

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NW 1/4 NW 1/4 SW 1/4 9 T 30 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 1/2 MILES SOUTH OF SUBLETTE

2 WATER WELL OWNER: ELTRUDE HALL
 RR#, St. Address, Box # : 104 W. EDELLE Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SUBLETTE, KS 67877- Application Number: 7,755

3 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 629 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \		WELL'S STATIC WATER LEVEL 303 ft. below land surface measured on mo/day/yr 09/02/94	
		Pump test data: Well water was 366 ft. after 2 hours pumping 1150 gpm	
1	NW NE	Estimated Yield 1150 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm	
W		Bore Hole Diameter 24 in. to 629 ft., and in. to 0 ft.	
e	SW SE	WELL WATER TO BE USED AS: 02 IRRIGATION	
Was a chemical/bacteriological sample submitted to department? No ;			
If yes, mo/day/yr sample was submitted		Water well disinfected? Yes	

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 629 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 357 ft. to 487 ft., From 0 ft. to 0 ft.
	From 599 ft. to 629 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 629 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	14	03 SILTY CLAY 07 FINE SAND			
14	22	01 CLAY 04 SANDY CLAY			
22	43	04 SANDY CLAY 07 FINE SAND			
43	66	04 SANDY CLAY			
66	90	LARGE GRAVEL 08 MEDIUM SAND 09 COARSE SAND			
90	166	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY			
166	336	01 CLAY			
336	355	01 CLAY 05 SAND			
355	365	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/31/94 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/07/94
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 041 HASKELL : NW 1/4 NW 1/4 SW 1/4 : 9 : T 30 S : R 32 W

2 WATER WELL OWNER: ELTRUDE HALL
RR#, St. Address, Box # : 104 W. EDELLE Board of Agriculture, Division of Water Resources
City, State, ZIP code : SUBLETTE, KS 67877- Application Number: 7,755

FROM	TO	LITHOLOGIC LOG
365	399	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
399	427	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
427	446	01 CLAY 04 SANDY CLAY 05 SAND
446	465	04 SANDY CLAY 05 SAND
465	487	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY
487	512	01 CLAY 04 SANDY CLAY 19 SHALE
512	602	19 SHALE 01 CLAY 20 LIMESTONE
602	626	23 SANDSTONE 19 SHALE
626	674	19 SHALE 31 CALICHE 23 SANDSTONE
674	680	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/31/94 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 09/07/94
under the business name of HENKLE DRILLING & SUPPLY by (signature)

Brady Reichmuth