

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	SW 1/4 SW 1/4 NE 1/4	10	T 30 S	R 33 W	

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 1/2 MILE SOUTH AND 3 1/2 MILES WEST OF SUBLETTE

2 WATER WELL OWNER:		DR. WARREN SWARTZ	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	2401 SCARBOROUGH DRIVE	Application Number: 12,805 27,708	
City, State, ZIP code :	ANCHORAGE, KS 99504-		

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 643	ELEVATION: 0
		Depth(s) Groundwater Encountered	1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 337 ft. below land surface measured on mo/day/yr 06/28/94	
Pump test data: Well water was 403 ft. after 4 hours pumping 726 gpm	
Estimated Yield 700 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm	
Bore Hole Diameter 24 in. to 643 ft., and in. to 0 ft.	
WELL WATER TO BE USED AS: POTABLE 02 Irrigation	
Was a chemical/bacteriological sample submitted to department? No ;	
If yes, mo/day/yr sample was submitted Water well disinfected? Yes	

5 TYPE OF BLANK CASING USED: 01 STEEL		CASING JOINTS: WELDED
Blank casing diameter 16 in. to 643 ft., Dia in. to 0 ft., Dia in. to 0 ft.		
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250		
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL		
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT		

SCREEN PERFORATED INTERVALS:	From 375 ft. to 475 ft., From 0 ft. to 0 ft.
	From 613 ft. to 643 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 643 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: NONE OBSERVED	
Direction from well?	How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	33	04 SANDY CLAY			
33	55	04 SANDY CLAY 31 CALICHE 20 LIMESTONE			
55	63	04 SANDY CLAY 05 SAND			
63	74	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
74	102	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
102	130	04 SANDY CLAY			
130	254	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
254	260	04 SANDY CLAY			
260	310	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/24/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/02/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)	
---	--

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 041 HASKELL : SW 1/4 SW 1/4 NE 1/4 : 10 : T 30 S : R 33 W

2 WATER WELL OWNER: DR. WARREN SWARTZ

RR#, St. Address, Box # : 2401 SCARBOROUGH DRIVE

Board of Agriculture, Division of Water Resources

City, State, ZIP code : ANCHORAGE, KS 99504-

Application Number: 12,805 27,708

FROM	TO	LITHOLOGIC LOG
310	325	07 FINE SAND 09 COARSE SAND 01 CLAY
325	350	01 CLAY
350	404	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
404	412	20 LIMESTONE
412	430	23 SANDSTONE
430	450	01 CLAY 20 LIMESTONE
450	612	19 SHALE
612	640	23 SANDSTONE
640	646	20 LIMESTONE 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/24/94 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 07/02/94

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Brue J. Reichmuth