

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 041 HASKELL NE 1/4 NW 1/4 NW 1/4 12 T 30 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 1 MILE SOUTH, 3/4 MILE WEST FROM SUBLETTE

2 WATER WELL OWNER: MASONER, RICHARD  
 RR#, St. Address, Box #: 7447 NORTH NORTHERN Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: TUCSON, AZ 85704- Application Number: 7,072 & 26,304

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

WELL'S STATIC WATER LEVEL 348 ft. below land surface measured on mo/day/yr 08/18/93  
 Pump test data: Well water was 409 ft. after 4 hours pumping 990 gpm  
 Estimated Yield 990 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 672 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 672 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 367 ft. to 387 ft., From 590 ft. to 670 ft.  
 From 400 ft. to 460 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 672 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? WEST How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	31 CALICHE 01 CLAY			
40	47	07 FINE SAND 08 MEDIUM SAND			
47	80	31 CALICHE 01 CLAY 07 FINE SAND			
80	90	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
90	120	04 SANDY CLAY			
120	132	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
132	145	01 CLAY 31 CALICHE			
145	387	07 FINE SAND 08 MEDIUM SAND 14 MED GRAVEL			
387	400	04 SANDY CLAY 20 LIMESTONE			
400	424	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/11/93 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/20/93  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

-(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number  
COUNTY: 041 HASKELL : NE 1/4 NW 1/4 NW 1/4 : 12 : T 30 S : R 33 W

2 WATER WELL OWNER: MASONER, RICHARD  
RR#, St. Address, Box #: 7447 NORTH NORTHERN  
City, State, ZIP code : TUCSON, AZ 85704-

Board of Agriculture, Division of Water Resources  
Application Number: 7,072 & 26,304

FROM	TO	LITHOLOGIC LOG
424	445	20 LIMESTONE 07 FINE SAND 01 CLAY
445	457	07 FINE SAND 09 COARSE SAND 20 LIMESTONE
457	476	23 SANDSTONE
476	580	19 SHALE 20 LIMESTONE
580	590	20 LIMESTONE 19 SHALE
590	670	23 SANDSTONE
670	675	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was  
completed on (mo/day/year) 08/11/93 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/20/93  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

*Bruce Reichmuth*