

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL SE 1/4 SE 1/4 NE 1/4 11 T 30 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 MILE WEST & 1 1/2 MILES SOUTH OF SUBLETTE

2 WATER WELL OWNER: HARRY WRIGHT FAMILY TRUST
 RR#, St. Address, Box #: PD BOX 1123 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LIVINGSTON, KS 59047-1123 Application Number: 30,542

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
NW	NE	SW	SE

4 DEPTH OF COMPLETED WELL 664 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 343 ft. below land surface measured on mo/day/yr 06/17/98
 Pump testdata: Well water was 380 ft. after 4 hours pumping 1100 gpm
 Estimated Yield 1100 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 664 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 664 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 370 ft. to 450 ft., From 0 ft. to 0 ft.
 From 499 ft. to 659 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 460 ft., From 0 ft. to 0 ft.
 From 460 ft. to 664 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	80	01 CLAY			
80	93	05 SAND 11 GRAVEL			
93	130	04 SANDY CLAY 20 LIMESTONE			
130	152	05 SAND 04 SANDY CLAY			
152	212	05 SAND			
212	217	04 SANDY CLAY			
217	245	05 SAND 11 GRAVEL			
245	275	01 CLAY			
275	307	05 SAND 11 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/11/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/26/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 041 HASKELL SE 1/4 SE 1/4 NE 1/4 11 T 30 S R 33 W

2 WATER WELL OWNER: HARRY WRIGHT FAMILY TRUST

RR#, St. Address, Box #: PO BOX 1123

Board of Agriculture, Division of Water Resources

City, State, ZIP code: LIVINGSTON, KS 59047-1123

Application Number: 30,542

FROM	TO	LITHOLOGIC LOG
307	332	01 CLAY
332	350	05 SAND 01 CLAY
350	410	05 SAND
410	419	05 SAND 11 GRAVEL
419	425	04 SANDY CLAY
425	433	05 SAND 11 GRAVEL
433	450	01 CLAY 20 LIMESTONE 19 SHALE
450	465	31 CALICHE 20 LIMESTONE
465	505	19 SHALE 01 CLAY
505	535	19 SHALE 31 CALICHE
535	659	23 SANDSTONE 19 SHALE
659	665	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/11/98 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/26/98

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Richmond